SUMMARY OF GUARDRAIL INSTALLATION & REMOVAL

LOCATION STA. TO STA. (℄ Survey.)	SIDE	GUARDRAIL (LF) ROADWAY P	GUARDRAIL (LF) ROADWAY F	GUARDRAIL (LF) REMOVAL P	GUARDRAIL (LF) REMOVAL F	END ANCHORAGE ASSEM. (EA) FLARED P	END ANCHORAGE ASSEM. (EA) FLARED F
782+38.98 to 783+63.63	LT	125.00				1	
782+38.98 to 783+63.63	RT	125.00				1	
784+89.46 to 788+52.00	LT			362.80			
35+56.07 to 48+68.57	LT			1314.00			
784+98.66 to 788+52.00	RT			354.40			
35+56.07 to 48+66.22	RT			1310.50			
50+36.38 to 51+60.97	LT	125.00				1	
152+36.46 to 153+47.95	RT	112.50				1	
TOTAL		487.50 LF		3341.70 LF		4 EA	

NOTE: ACTUAL LENGTHS ARE GREATER THAN CALCULATED LENGTHS ALONG ℄ SURVEY DUE TO FLARED END SECTIONS.

SUMMARY OF EARTHWORK

DESCRIPTION	P CU.YD.	F CU.YD.
REGULAR EXCAVATION		
SR 30	1,694	
AUCILLA LANDING RD.	257	
SR 30 FLOODPLAIN COMPENSATION	2,185	
TOTAL REGULAR EXCAVATION	4,136	
EMBANKMENT		
SR 30	5,740	
AUCILLA LANDING RD.	190	
TOTAL EMBANKMENT	5,930	

SUMMARY OF PERMANENT CRASH CUSHIONS

LOCATION STATION	SIDE	DESIGN SPEED	CRASH CUSHION (EA) OPTIONAL P	CRASH CUSHION (EA) OPTIONAL F
47+78.59	LT	65	1	
302+00.00	LT	30	1	
		TOTAL =	2	

SUMMARY OF FENCE GATE TYPE B

LOCATION STA.	SIDE	LENGTH (FT) P	LENGTH (FT) F	REMARKS	FIELD BOOK REFERENCE
11+61.19 ℄ Access Rd.	LT/RT	10'			

SUMMARY OF LITTER REMOVAL AND MOWING

CONST. PHASE	DURATION (DAYS)	FREQUENCY (DAYS)	LITTER REMOVAL CYCLES	LITTER REMOVAL AREA AC/CYCLE	LITTER REMOVAL AREA TOTAL (AC)	MOWING CYCLES	MOWING AREA AC/CYCLE	MOWING AREA TOTAL (AC)	REMARKS
ALL	1	60	1	4.2	4.2	1	4.2	4.2	
			TOTAL	P / F	4.2	TOTAL	P / F	4.2	

NOTE: CYCLES WILL BE CALCULATED WHEN THE DURATION (DAYS) IS RECEIVED FROM THE FDOT CONSTRUCTION OFFICE.

SUMMARY OF PERFORMANCE TURF

LOCATION	SIDE	P SY	F SY	FIELD BOOK REFERENCE
SR 30 (Floodplain Compensation area)				
(1994.5 + 10% Increase)		2194		
TOTAL		2194		

SUMMARY OF PERFORMANCE TURF, SOD

LOCATION	SIDE	P SY	F SY	FIELD BOOK REFERENCE
SR 30 (8599 + 10% Increase)		9,459		
AUCILLA LANDING RD. (170 + 10% Increase)		187		
TEMP. SOD (TCP) (8354 + 10% Increase)		9,189		
TOTAL		18,835		

SUMMARY OF LANDSCAPING

TYPE	P EA	F EA	REMARKS
3 GALLON TREES (SMALL PLANT)	489		SEE WETLAND RESTORATION PLAN FOR TEMPORARY
7 GALLON TREES (LARGE PLANTS)	488		FILL AREAS PLAN SHEETS FOR DETAILS

SUMMARY OF REMOVAL OF EXISTING CONCRETE PAVEMENT

STATION TO STATION	AREA (SY) P	AREA (SY) F	DESCRIPTION
786+30.00 to 786+60.00	93.3		Approach Slabs
40+63.50 to 40+93.50	93.3		Approach Slabs
43+91.40 to 44+21.40	93.3		Approach Slabs
47+05.90 to 47+35.90	93.3		Approach Slabs
SUB-TOTAL	373		

PAY ITEM NOTES

102-1 Includes the removal of traffic control striping for all phases. Includes two Project Information Signs and six "CAUTION BRIDGE WORK" signs shown in the Traffic Control Plans. Includes removal of markings that conflict with the final striping plan that are outside the limits of construction (narrow bridge markings) and milling & resurfacing.

102-2-1 Includes all construction associated with the temporary detour bridge, including maintenance and removal. Includes 21,076 CY of temporary embankment and removal, 29 CY of excavation for the diversion and temporary roadway on Aucilla Landing Rd. Includes 10,090 SY of temporary pavement. Includes the cost of 153 LF of temp. 18" pipe, 2 EA temp. DBI's and 4 EA temp. 18" Mitered End Sections as shown in the Traffic Control Plans.

104-15 Includes 2-36' X 100' temporary stabilization areas at the entrance and exit of temporary work platform. Areas are based on multiples of the 12' X 50' minumum size from the Florida Erosion and Sediment Control Manual.

110-1-1 Includes the cost of the removal of 41 object markers shown in the signing and pavement marking plans.

570-1-2 Includes 9,189 SY of Sod for temporary erosion control.

580-1-X Includes the cost of maintaining or modifying the existing erosion control plan for the wetland restoration plan after construction.

710- The totals shown on the Summary of Roadway Pay Items are for painted pavement markings used for Maintenance of Traffic.

REVISIONS DATE	DESCRIPTION	DATE	DESCRIPTION

ECDriver & Associates 1983 CENTRE POINTE BLVD. SUITE 104 TALLAHASSEE, FL 32308-7823 CERT. OF AUTH. #3838
ENGINEER OF RECORD: Derek A. Johnson, P.E. P.E. NO. 62422

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

ROAD NO.	COUNTY	FINANCIAL PROJECT ID
SR 30	TAYLOR	210873-2-52-01

SUMMARY OF QUANTITIES

SHEET NO. 6

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.003, F.A.C.