ENGINEER'S FIELD OFFICE. (REV 1-4-11) (FA 2-17-11) (1-13)

PAGE 148. The following new Section is added after Section 107:

SECTION 109 ENGINEER'S FIELD OFFICE

109-1 Description.

Provide, furnish, and maintain an Engineer's Field Office for exclusive use by the Department. When applicable, Uuse Type B Fencing as detailed on Design Standards, Index No. 452, to enclose the field office. Place the fence at least 35 feet from the front and 5 feet from the other three sides of the field office. Place one 4 foot gate and one 12 foot gate at locations designated by the Engineer. The site of the field office location shall include appropriate exterior lighting for security.

109-2 Office Requirements.

109-2.1 General Requirements: The field office shall be a building or mobile trailer erected at a location selected by the Engineer and shall be separate from any building used by the Contractor.

The office ceiling height shall be at least 7 feet with a minimum floor space as specified in the plans. The total floor area shall be partitioned according to the following table:

Minimum Total Area Required	# of small rooms ¹	# of large rooms ²	# of restrooms					
300 ft ²	1	1	-					
600 ft^2	2	2	1					
900 ft ²	3	2	1					
1,200 ft ²	5	3	2					
1,500 ft ²	6	4	2					
Ismall rooms shall have a minimum floor area of 90 ft ² . 2 large rooms shall have a minimum floor area of 150 ft ² .								

Each room shall have at least one weatherproof window, and two electrical outlets, one telephone outlet, and one Category 5 Ethernet outlet. Each window shall have a minimum area of 8 square feet, be screened and open and close to provide adequate ventilation. Equip each outside door with a lock.

The Engineer may approve an equivalent facility provided it meets the minimum specified requirements.

109-2.2 Equipment and Furniture: Include the following equipment and furniture:

Item	Office Size (ft ²)					
item	300	600	900	1,200	1,500	
	Electric light, non-glare type luminaires to provide a					
(a) Lighting	minimum illumination level of 100 ft·cd at desk height					
	level.					

Formatted: Font color: Red

	τ.	Office Size (ft ²)					
	Item	300	600	900	1,200	1,500	
	(IN Harding and Carling	Adequate equipment to maintain an ambient air					
	(b) Heating and Cooling	temperature of 70 ± 5 °F.					
	(c) Desks (with drawers and locks)	1	3	5	8	10	
	(d) Office chairs	1	3	5	8	10	
	(e) Stackable chairs	4	8	10	12	16	
l	(f) Conference chairs	<u>8</u>	<u>8</u>	<u>8</u>	<u>16</u>	<u>16</u>	
	(fg) Fire Resistant Cabinet: fire resistant, legal size, four drawer, with lock and two keys, meeting the requirements for "Filing Devices, Insulated (36E9)" Class D Label, of the Underwriters' Laboratories, Inc. Specifications	2	2	3	3	4	
	(g) Drafting type tables: each 3 by 6 feet, supported by wall brackets and legs	3	3	4	4	5	
	(h) Telephones with teleconferencing capability including speaker phone Draftsman's stools	3 2	3 2	4 <u>3</u>	4 <u>5</u>	5 <u>6</u>	
	(i) Office Table: each 3 by 6 feet	1	1	2	2	3	
ļ	(j) Conference Table: each 3 by 12 feet	<u>1</u>	<u>1</u>	<u>1</u>	<u>2</u>	<u>2</u>	
	(jk) Plans Racks: vertical filing plan racks for four sets of 11 by 17 inch plans	1	1	1	2	2	
	(1) All in one copier, facsimile, scanner machine, and printer	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	<u>1</u>	
İ	(km) Potable Water or Water Cooler	If cooler is used, maintain adequate water supply.			ply.		
	(½n) Restroom	An enclosed room with toilet, sink with running water (can be nonpotable) and with proper sewer connection or septic tank. Number of restrooms as specified in 109-2.1.					
		A room large enough to store surveying instruments and testing equipment. Provide the room with lock and electrical outlet.					
		Maintain all facilities and furnished equipment in good working condition.					
	(og) File Extiliguisher:	Two, 5 pound, non-toxic, dry chemical, fire extinguishers meeting Underwriters' Laboratories, Inc.,					
		Provide adequate security of all facilities and furnished equipment.					

109-2.3 Occupancy and Maintenance: Provide a field office for Department use, beginning 30 calendar days before Contract Time begins and remaining for 30 calendar days after final acceptance, unless the Department requests removal earlier.

Comment [AUTRY 1]: Debbie, it appears something is missing here. Who would know which Underwriter Laboratory requirements need to be met?

Do not begin work before the field office is available for Department use.

Maintain the field office in good condition and appearance, inside and out. The Department will provide janitorial services and supplies, including paper supplies for the restrooms. After the designated period, remove all portable buildings or trailers, equipment, furniture, fencing, surfacing, and utilities. and ILeave the areas with a finish soil layer cleaned, and seeded, if required, and in an acceptable condition. Retain ownership of the facility.

Early removal requests by the Department will be in writing and provide not less than ten days notice to the Contractor.

109-3 Compensation.

Payment will be made for each day the field office is available for use by Department personnel during the period described in 109-2.3. Price and payment will be full compensation for all labor, material, equipment, furniture, lease fees, electrical service charges, water service charges, and utility sewer service charges, and telephone and internet provider charges necessary to provide, furnish, maintain, and remove the field office, furniture, and equipment. The Department will pay all telephone charges.

Payment will be made under:

Item No. 109-71- Field Office - per day.