



Florida Department of Transportation

CHARLIE CRIST
GOVERNOR

719 South Woodland Boulevard
DeLand, Florida 32720

STEPHANIE C. KOPELOUSOS
SECRETARY

DESIGN MEMORANDUM 08-02

Date: July 9, 2008

To: Designers and Project Managers

From: Annette K. Brennan, P.E., District Design Engineer *AKB*

Copies: Frank O'Dea, Mario Bizzio, Mark Robinson, Ed Kestory, Technical Support and Production Support Staff

Subject: **Driveway Maintenance During Construction**

Effective with the January 2009 letting commercial material for driveway maintenance will be included in the plans under pay item 102-1 Maintenance of Traffic - Lump Sum, without quantities in the plans. Reclaimed asphalt pavement (RAP) (minimum 4" thickness) shall be used at all driveways except those specifically identified in the plans as requiring temporary asphalt pavement. Temporary asphalt connections (minimum 2" thickness) will be included in the plans under pay item 102-1 Maintenance of Traffic - Lump Sum, also without quantities in the plans. For computation book purposes the designer will be responsible for calculations for the total number of driveway connections with an average width and length. The following pay item note is to be included in the plans.

102-1 Includes the cost of furnishing, placing, maintaining and removing reclaimed asphalt pavement (RAP) surface material (minimum 4" thickness) for driveway maintenance throughout all phases of construction at all driveways, except those specifically noted in the plans to have temporary asphalt pavement. Includes the cost of furnishing, placing, maintaining and removing temporary asphalt pavement (minimum 2" thickness) at driveways and other locations as indicated in the plans.