

CONSTRUCTION PROJECT ADMINISTRATION MANUAL (CPAM)

Table of Contents

Introduction	i
Introduction for Final Estimates Process	ii

PRE-CONSTRUCTION

Chapter-1 PRE-LETTING ACTIVITIES

1.1 Plans Review and Comments	1-1-1
1.2 Contract Duration and Alternative Contracting Techniques	1-2-1
1.3 Pre-Bid Questions and Answers	1-3-1

Chapter-2 OFFICE PREPARATION

2.1 Project Scheduling	2-1-1
2.2 Final Estimates Pre-Planning.....	2-1-2

Chapter-3 PRE-CONSTRUCTION ACTIVITIES

3.1 Pre-Construction Conference.....	3-1-1
3.2 Quality Assurance and Quality Control of Field Operations	3-2-1
3.3 Contractor's Quality Control Plan	3-3-1
3.4 Dispute Review Board.....	3-4-1
3.5 Quality Assurance Review for Final Estimates.....	3-5-1

Chapter-4 CONSULTANT CEI MANAGEMENT

4.1 Administration of Consultant CEI Contracts	4-1-1
4.2 Consultant CEI Accountability	4-2-1

CONSTRUCTION

Chapter-5 PROJECT DOCUMENTATION

5.1 Project Diary.....	5-1-1
5.2 Contractor Vehicle Registration.....	5-2-1
5.3 Subletting of Contract.....	5-3-1
5.4 Contract Wage Requirements	5-4-1
5.5 Equipment Rental.....	5-5-1
5.6 Utility Relocation	5-6-1
5.7 Federal Aid Project Requirements	5-7-1
5.8 Control of Materials.....	5-8-1
5.9 Process Review of Construction Engineering & Inspection.....	5-9-1

5.10	Verification Inspection and Testing	5-10-1
5.11	Final Estimates Documents	5-11-1
5.12	Final "As-Built" Plans	5-12-1
5.13	Computation Books	5-13-1
5.14	Field Records	5-14-1
5.15	Final Measurements	5-15-1
5.16	Earthwork Notes and Documentation	5-16-1

Chapter-6 CONTRACT PAYMENTS

6.1	Unpaid Bills Processing.....	6-1-1
6.2	Alternative Contracts Invoices & Payments	6-2-1

Chapter-7 CONTRACT MODIFICATIONS

7.1	Post Award Plan and Contract Changes	7-1-1
7.2	Time Extensions.....	7-2-1
7.3	Supplemental Agreements and Unilateral Payments.....	7-3-1
7.4	Contingency Supplemental Agreements and Work Orders.....	7-4-1
7.5	Construction Contract Claims.....	7-5-1
7.6	Contracting for Governor Declared Emergencies	7-6-1

Chapter-8 ADMINISTRATIVE REQUIREMENTS

8.1	F.A.I.N. Resolution	8-1-1
8.2	Environmental Commitment Compliance	8-2-1
8.3	Operation Within Railroad Right-of-Way	8-3-1
8.4	Shop and Erection Drawing Approval	8-4-1
8.5	Contract Delinquency	8-5-1
8.6	Contract Default	8-6-1
8.7	Contractor Non-Responsibility For Construction Contract.....	8-7-1
8.8	State Arbitration Board.....	8-8-1
8.9	Contract Termination.....	8-9-1
8.10	Noise and Vibration Abatement.....	8-10-1
8.11	Contractor Initiated Submittals	8-11-1
8.12	Joint Participation Agreements	8-12-1

Chapter-9 MAINTENANCE OF TRAFFIC

9.1	Maintenance of Traffic (MOT)	9-1-1
9.2	Work Zone Regulatory Speeds	9-2-1
9.3	Work Zone Traffic Incident Evaluation and Reporting	9-3-1

Chapter-10 STRUCTURES

10.1	Pile Lengths	10-1-1
10.2	Pre-stressed / Pre-cast Concrete Components.....	10-2-1
10.3	Concrete Construction	10-3-1
10.4	Paint and Asbestos Removal Handling and Disposal	10-4-1
10.5	Drilled Shafts.....	10-5-1
10.6	Underwater Bridge Construction Inspection	10-6-1

[Table of Contents](#)

Revised:

10.7	Post-Tensioned Bridges	10-7-1
10.8	Auger Cast Piles	10-8-1
10.9	Structural Steel and Miscellaneous Metal Components.....	10-9-1
10.10	Bridge Construction Issues that Must Involve Office of Construction Staff	10-10-1
10.11	General Structures Construction Issues.....	10-11-1

Chapter-11 ASPHALT

11.1	Asphalt Quality Assurance (QA) Referee System for Non-QC-2000 Projects	11-1-1
11.21	Asphalt Plant Operations.....	11-1-1
11.2	Asphalt Mix Temperature Control.....	11-2-1
11.3	Asphalt and Other Base Courses – Categorizing.....	11-3-1
11.4	Adjustments	11-4-1
11.5	Testing and Correction of Surface Deficiencies on Asphalt Pavement	11- 25 -1
11.6	Documentation for Multiple FIN Projects	11-6-1
11.7	Contractor’s Quality Control(CQC).....	11-7-1
11.8	Submittals	11-8-1
11.9	Salvage of Materials.....	11-9-1

POST-CONSTRUCTION

Chapter-12 PROJECT CLOSEOUT

12.1	Project Acceptance	12-1-1
------	--------------------------	--------

Chapter-13 PERFORMANCE RATINGS

13.1	Contractor’s Past Performance Rating	13-1-1
13.2	Constructability Grades	13-2-1
13.3	Contractor Survey	13-3-1