

Florida Department of Transportation

CHARLIE CRIST
GOVERNOR

605 Suwannee Street
Tallahassee, Florida 32399-0450


STEPHANIE C. KOPELOUSOS
SECRETARY

August 25, 2009

This Memo Has Expired

DCE MEMORANDUM NO: 17-09
(FHWA Approved: 8-24-09)

TO: DISTRICT CONSTRUCTION ENGINEERS
DISTRICT DESIGN ENGINEERS

FROM: David A. Sadler, P.E., Director, Office of Construction 

COPIES: Brian Blanchard, Lora Hollingsworth, Chris Richter (FHWA),
Chad Thompson (FHWA), Bob Burleson (FTBA)

SUBJECT: CORRECTION TO SP0060100LS – SPECIFICATIONS WORKBOOK
2010

As part of the July 2009 specifications Workbook, SP0090103LS was updated deleting section 9-11.1 and 9-11.2 with this information being placed in section 105 of the Supplemental Specifications for the July 2009 Specifications Workbook. As a result of this change, references to section 9-11.1 and 9-11.2 were inadvertently missed in SP0060100LS. As a result, SP 0060100LS has been updated and will be included in the January 2010 Specifications Workbook.

The changes to SP0060100LS are shown below.

6-1.3.3 of the Special Provision should read as follows (change noted in red):

6-1.3.3 Lump Sum Project General Requirements: Material is accepted by material sampling and testing requirements for the following work activities: Earthwork and Related Operations, Base Courses, Hot Bituminous Mixtures, Portland Cement Concrete, and Reinforcing Steel as stated in **105-2**. Fabricated metal acceptance will be in accordance with **105-1.2.3**. All other material acceptance will be in accordance with 6-1.

For all Lump Sum projects let from July 2009 through December 2009, this memorandum serves as a blanket approval to process a contract change to include this revision. A copy of this memorandum should be attached to the Supplemental Agreement.

If you have any questions regarding this memorandum, contact Paul Steinman at 850-414-4140.

DS/sw