

VanLandingham, Roger

From: VanLandingham, Roger
Sent: Tuesday, September 30, 2014 2:49 PM
Subject: Addendum 1 - Project #427553-5-52-01, FCO E9085

Importance: High

Addendum #1 FCO E9085

Listed below is information from the Mandatory Pre-Bid Meeting that was held on September 23, 2014.

Please acknowledge receipt of the email. Please notate Addendum #1 on the Bidding Document.

Roger Van

Roger VanLandingham
Systems Analyst
Contracts Administration, FL DOT
(850) 414-4002
FAX (850) 414-4947
roger.vanlandingham@dot.state.fl.us

Mandatory Pre-Bid Meeting for Proposal E9085 September 23, 2014

1. Insurance Requirements – Look in Section B of standard FDOT Specs. Make sure that DOT is listed as Additional Named Insured. Endorsement Page is needed.
2. Bid Bonds -

Bids \$100,000.00 and over must have Bid Bond.

Bids under \$100,000.00 Bid Bond not required.

3. Performance Bond and Labor and Materials Bond –

Bids \$100,000.00 and over must have Performance Bond and Labor and Materials Bond

Bids under \$100,000.00 Performance Bond and Labor and Materials Bond not required.

4. Subcontractors list is NOT required with bid. However Subcontractors list shall be provided to Project Manager in writing 14 days before work begins. DOT must approve the use of any Subcontractor.
5. General Contractors or Builder's License is required before or with BID Documents.
6. Winning bidder shall have an "Active Vendor Number and approved W9 prior to Department encumbering (committing) funds for award.
Bidder shall register at www.myfloridamarketplace.com, if vendor doesn't not active vendor number.
7. Bid opening in Tallahassee FL. On October 15 2014, at 2:00 PM. NO LATE PRICE PROPOSALS SHALL BE ACCEPTED.
8. Selected bidder shall provide the Project Manager (Ken Cox) a certification from the metals or roof manufacturer that the installer is qualified to install metal canopies (See #4, above).
9. The structure shall be steel – galvanized and color of finish shall be same as existing roof.
10. FDOT shall verify whether or not the roof needs to be insulated or not.
11. There will be a "pre-construction meeting" after the vendor is selected and before vendor begins construction or ordering supplies.
12. Contractor shall use engineering calculations (hire an engineer) to ensure that local building code wind load requirements are met.
13. Contractor shall provide waste collection units ((dumpster (s)) and Portolets (restrooms) for workers at their cost. Location of each shall be selected by FDOT Project Manager.
14. FDOT will provide normal (110 v, 208 v) and water. Any "special" needs shall be provided by contractor.
15. Contractor is responsible to pull and pay for all local permits needed to complete the job.
16. Size of canopy at chiller plant can be increase to locate foundations off of existing slab if needed.
17. Roof insulation is not needed for this project

18. Wet saw canopy is to clear windows and still meet 10' minimum height
19. Re: Note N13 - Starting at trench, north slab is to slope up towards building and south slab is to slope up to be flush with existing pavement. Intent is for the new sections of slab to slope towards new trench drain.