

Proposal ID:	T5388
Project Number:	424900-1-52-01
County:	Seminole
Road:	US 17/92
Limits:	From a point North of Raven/Shepherd Rd to Lake Mary Blvd
Description:	The improvements under this contract consist of milling and resurfacing, ADA upgrades, signing and pavement markings and replacing loops at signalized intersections of SR 15/600.

Question	Response
<p><u>Posted: Tuesday, 07/05/2011 @ 08:35am - MRS</u></p> <p>1) The QTY for Detectable Warning Retrofits appears to be higher than what's shown in the plans, it appears some locations of new sidewalk construction call for the Retrofits, however for new construction the cost of the Detectable Warning is typically included in the sidewalk. Are the detectable warnings on new sidewalk construction being paid for separately from the sidewalk itself for this contract?</p>	<p><u>Posted: Tuesday, 07/19/2011 @ 10:00am - JMD</u></p> <p>1) Detectable warnings are typically included in new curb ramp construction. However, most of the corridor does not have curb and gutter, so we could not call these areas "curb ramps" and felt we should call out detectable warnings to be installed as part of the sidewalk construction.</p> <p>There are three locations that do include curb and gutter at Weldon, County Home, and N Bush/Tropic and it is expected that detectable warnings would be included at those areas as well, even though they are not called out for in the plans.</p>
<p><u>Posted: Thursday, 07/07/2011 @ 08:30am - MRS</u></p> <p>2) Page 6 of the plans in the typical sections under Superelevation Correction Limits call for milling of 4" average depth, there isn't a pay item for this milling thickness.</p>	<p><u>Posted: Tuesday, 07/19/2011 @ 10:00am - JMD</u></p> <p>2) What you are describing is not on page 6 of the plans. Please review your contract documents.</p>
<p><u>Posted: Wednesday, 07/13/2011 @ 08:34am - MRS</u></p> <p>3) Plans call to relocate the existing TMS cabinet under item 746-75 but on sheet T-13 under Standard Notes for TMS reads to furnish and install a base mount type III with J and P and ARD 2000 wiring harness. Please clarify. If the existing TMS cabinet is relocated will the J, P, and ARD 2000 wiring harness need to be included?</p>	<p><u>Posted: Tuesday, 07/19/2011 @ 10:00am - JMD</u></p> <p>3) The notes on T-13 are the standard notes that we include on all projects with TMS sites. The intent was to relocate the existing cabinet, not to furnish and install a new one. No additional harnesses are needed.</p>
<p><u>Posted: Wednesday, 07/20/2011 @ 08:42am - MRS</u></p> <p>4) I don't see a pay item note for the 710-90 for thermoplastic is this job 2 coats of paint</p>	<p><u>Posted: Thursday, 07/21/2011 @ 09:10am - MRS</u></p> <p>4) Yes.</p>