



Bid Questions and Answers Report

Date & Time:

12/5/2012 9:26:17 AM

District Address: District 1 Construction Office, located at 801 N Broadway, Bartow, FL 33830

District Phone: (863) 519-2222

Proposal: T1523

Project: 425229-1-52-01

Letting Date: 12/5/2012

Location: CENTRAL OFFICE

Description: SR 78

---

Question: 2035: Upon review of Sheet 5, Summary table for Turnout construction; it is noted that the turnouts are to receive 1.5" TL D 76-22. However, a review of Sheets 51-53, Driveway details; indicate complete remove/replace of those driveways (turnouts) to be reconstructed with OBG 1 and 1.5" TL C. Which type mix is required in these 7 locations?

Posted: 11/27/2012 3:41:05 PM

---

Answer: The seven (7) Turnout locations will be reconstructed with OBG 1 and 1.50 inches of Traffic Level "D" 76-22."

Status: ANSWER PUBLISHED

Posted: 11/29/2012 5:09:17 PM

---

Question: 2036: Sheets 51-53 show the Driveway/Turnout details; can the department provide any existing core or pavement sections for these areas? Also, is there a Pavement Condition or analysis report available for contractors information?

Posted: 11/27/2012 3:55:32 PM

---

Answer: The department does not have pavement evaluations/cores for any driveways.

Status: ANSWER PUBLISHED

Posted: 11/28/2012 5:40:34 PM