



Bid Questions and Answers Report

Date & Time:

4/25/2013 1:37:20 PM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4355

Project: 427022-1-52-01

Letting Date: 4/24/2013

Localtion: CENTRAL OFFICE

Description: SR 510 (WABASSO RD)

Question: 3386: Plan sheet T-4 has a description in the middle of the intersection picture that reads, "Exist. F.O. Pull Box to be Replaced and Relocated to the back of sidewalk". Is the existing fiber going to be long enough to allow this? If so, can split duct be used to re-route the conduit or does the fiber need to be disconnected and pulled back in? Posted: 4/9/2013 8:06:10 AM

Answer: There is enough slack in the existing pull box to allow for the relocation of the existing fiber cabling to be relocated to the new pull box location at the back of sidewalk. Yes, either a split duct installation or disconnecting and pulling the fiber optic cabling back into a new conduit to the new pull box location is approved in accordance with Indian River County Traffic requirements. The contractor shall include all costs incidental to reroute the fiber optic cable and conduit installation in pay item 635-1-15. Status: ANSWER PUBLISHED
Posted: 4/9/2013 4:29:05 PM