



Bid Questions and Answers Report

Date & Time:

3/27/2013 2:01:06 PM

District Address: District 3 Construction Office, located at 1074 Highway 90 East, Chipley, FL 32428

District Phone: (850) 415-9713

Proposal: T3350

Project: 407168-1-52-01

Letting Date: 3/27/2013

Localtion: CENTRAL OFFICE

Description: SR 20

---

Question: 2744: 1. Sheet B1-6, Permanent Casing Table Note 2 "Construct the test shaft in the same manner and to the same requirements as a production shaft", but the pay item 0455 107 Drilled Shaft Casing does NOT include the quantity for the test shaft. Does the test shaft require Permanent Casing? If yes, how long? In which pay item is the cost to be included? Posted: 3/1/2013 7:43:46 AM

---

Answer: Permanent casing is not required for the test shaft. Status: ANSWER PUBLISHED

Posted: 3/8/2013 2:19:26 PM

---

Question: 2745: 2. Is an Axial Shaft Load Test required for the test shaft? If yes, what type? And which pay item? Posted: 3/1/2013 7:45:15 AM

---

Answer: Axial shaft load test is not required. Status: ANSWER PUBLISHED

Posted: 3/8/2013 2:16:18 PM

---

Question: 2746: 3. For MCI/Verizon utility hangers, there are 2 different details on sheet B1-34 and B1-35, please instruct which one to use? Also please provide spacing information for this hanger. Posted: 3/1/2013 7:47:00 AM

---

Answer: The details shown on Sheet B1-34 are for the "braced", or "anchor" hangers and the details on Sheet B1-35 are for "intermediate" hangers. Status: ANSWER PUBLISHED

Posted: 3/8/2013 3:20:06 PM

---

Question: 2747: 4. Sheet B1-26, is the contractor responsible for installing the utility hangers under the bridge? The payment note on this sheet stipulates only the conduit. Posted: 3/1/2013 7:48:54 AM

---

Answer: The conduit and associated hangers and hardware (as required) are to be provided to the contractor by the individual utilities. The contractor is responsible for all installation. Payment for the installation is to be included in pay item number 521-5-1.

Status: ANSWER PUBLISHED

Posted: 3/8/2013 11:28:54 AM