



Bid Questions and Answers Report

Date & Time:

3/27/2013 2:11:30 PM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4344
Project: 424674-1-52-01
Letting Date: 3/27/2013
Location: CENTRAL OFFICE
Description: SR 822 (SHERIDAN ST)

Question: 3000: What are the quantities of excavation and embankment for pay item #521-72-3 Shoulder Concrete Barrier Wall as denoted on the pay item notes found on sheet number 17 of the contract documents. Posted: 3/20/2013 11:03:36 AM

Answer: In response to the bid question, the quantities for excavation and embankment for Shoulder Concrete Barrier Wall (pay item # 521-72-3) are as follows; Excavation: 181 CY (SR 822 Sta. 21+25 to Sta. 26+25), 138 CY (I-95 SB Off-Ramp Sta. 2+80 to Sta. 3+65), 27 CY (SR 822 Sta. 607+84 to Sta. 608+35) TOTAL = 345 CY. Embankment: 194 CY (SR 822 Sta. 21+25 to Sta. 26+25), 149 CY (I-95 SB Off-Ramp Sta. 2+80 to Sta. 3+65), 40 CY (SR 822 Sta. 607+84 to Sta. 608+35) TOTAL = 383 CY.

All costs for excavation and embankment work to construct Shoulder Concrete Barrier Wall is incidental to pay item 521-72-3 and should be included in the unit cost of the Shoulder Concrete Barrier Wall.