



Bid Questions and Answers Report

Date & Time:

3/27/2013 2:12:47 PM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4361

Project: 431802-1-52-01

Letting Date: 3/27/2013

Location: CENTRAL OFFICE

Description: (DISTRICT-WIDE TRAFFIC SIGNAL HANGER RETROFIT)

---

Question:	2902: I-Please clarify scope of work (special provision Article 4-1). Is it limited to the replacement of the signal hanger which should include? 1- New pivotal adjustable hanger assembly including messenger cable clamp. 2- Reinforcement of ceiling and floor of disconnect. 3- Reinforcement of the ceiling of signal heads, and 4- Reinforcement of ceiling of bracket on a 4 and 5 signal head assembly. 5- Replace disconnect if it is direct threaded. 6- Replace flat hanger if existing is cable or pipe type. 7- Replace saddle clamps, disconnects, and tri-stub hubs if required depending on condition and CEI evaluation.  Or. Should items 5, 6, and 7 be considered under special provision Article 4-3.1(significant change) or Article 4-3.4(unforeseen work or alterations)?  II- Drawings are showing Index No. 17727. Is this for reference only? Or Will this means that contractor shall bring	Posted: 3/18/2013 12:49:01 PM
-----------	--	-------------------------------

---

Answer:	Response for Items 1 through 7; refer to plan sheet T-14 for scope of work to be completed.  In addition the following clarifications are added; Plan Sheet T-14 General Note 1 is deleted and substituted with the following "Note 1 - Shall be replaced with new". Plan Sheet T-14 General Note 5 shall be modified as follows "Note 5 - Installation will require removal or reconnection of electrical components".	Status: ANSWER PUBLISHED  Posted: 3/22/2013 3:45:17 PM
---------	---	--

Answer:	<p>1- New pivotal adjustable hanger assembly including messenger cable clamp. Response: Yes 2- Reinforcement of ceiling and floor of disconnect. Response: Yes 3- Reinforcement of the ceiling of signal heads, and Response: Yes for Red indication only 4- Reinforcement of ceiling of bracket on a 4 and 5 signal head assembly. Response: Yes for 5 section only. 5- Replace disconnect if it is direct threaded. Response: Yes 6- Replace flat hanger if existing is cable or pipe type. Response: Yes. Flat hangers will replace exiting cable or pipe. Any existing flat hangers will be replaced or modified 7- Replace saddle clamps, disconnects, and tri-stub hubs if required depending on condition and CEI evaluation. Response: Saddle clamps and disconnect hangers will be replaced. Tri-stub hubs will be removed as per detail. Or. Should items 5, 6, and 7 be considered under special provision Article 4-3.1(significant change) or Article 4-3.4(unforeseen work or alterations)? Response: Items 5 and 7 are under special provisions. Item 6 is part of scope of work.</p>	Status: ANSWER VOIDED
		Posted: 3/22/2013 11:04:25 AM
Question:	<p>2920: II- Drawings are showing Index No. 17727. Is this for reference only? Or Will this means that contractor shall bring existing pole grounding and Span wires assemblies up to new standards as required? If required. Will this work be part of special provision Article 4-3.1(significant change) or Article 4-3.4(unforeseen work or alterations)?</p>	Posted: 3/18/2013 2:17:17 PM
Answer:	<p>Response: The index references only the pivotal hanger assembly. The second sheet</p>	Status: ANSWER PUBLISHED
		Posted: 3/21/2013 5:53:52 PM
Question:	<p>2921: II- Drawings are showing Index No. 17727. Is this for reference only? Or Will this means that contractor shall bring existing pole grounding and Span wires assemblies up to new standards as required? If required. Will this work be part of special provision Article 4-3.1(significant change) or Article 4-3.4(unforeseen work or alterations)?</p> <p>III- In reference to drawing T-3 Traffic control notes 7. Please clarify if contractor will need to replace at its own expense any traffic Signal Head assembly that does not meet current Broward County Traffic Engineering Division Standard including adding missing back plates and tuner visors, defective brackets or housing or LED modules, etc. If required, will this work be part of special provision Article 4-3.1(significant change) or Article 4-3.4(unforeseen work or alterations)?</p>	Posted: 3/18/2013 2:18:04 PM
Answer:	<p>Response to II- The index references only the pivotal hanger assembly on the second sheet.</p>	Status: ANSWER PUBLISHED
	<p>Response to III- No, but the contractor is responsible for all costs to replace any materials if damaged by the contractor.</p>	Posted: 3/22/2013 11:48:51 AM