



Bid Questions and Answers Report

Date & Time:

5/5/2014 1:09:23 PM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4389  
Project: 230978-2-52-01  
Letting Date: 4/30/2014  
Location: CENTRAL OFFICE  
Description: CR 714 (MARTIN HWY)

---

Question: 6662: Can you supply the plans in the old PDF format. The new format is harder to print. Posted: 4/1/2014 9:32:15 AM

---

Answer: The format submitted is the Official format. We cannot submit in a different format. Status: ANSWER PUBLISHED

Posted: 4/7/2014 3:03:16 PM

---

Question: 6849: The pumpstation specifications does not call out a specific model or make. Is there a certain manufacturer? Hoover? Flowtronics? Posted: 4/14/2014 1:20:49 PM

---

Answer: Pump model (Hoover Pumping model: HCF-10PDV-230-E-18, L,M,S,Z) has been provided in Irrigation Details Sheet. See sheet number LD-28. Status: ANSWER PUBLISHED

Posted: 4/14/2014 3:23:52 PM

---

Question: 6856: Per sheet 25, pay item notes 522-2; the quantity of 6' wide x 25' long sidewalk (both sides of ATT & FPL poles) is not included in the bid item, but must be calculated by us and then increased? Posted: 4/14/2014 3:38:30 PM

---

Answer: The quantity is already included in payitem 522-2. Status: ANSWER PUBLISHED

Posted: 4/15/2014 3:55:38 PM

---

Question: 6863: I cannot tell from the Creek typical section detail on sheet 37 what the amount of earthwork to establish and maintain a 1:2 slope at the Danforth creek is, as stated on sheet 25 pay item notes for item 530-3-3. Could you please provide that quantity so that we can include it in the cost of the riprap-rubble, bank and shore? Posted: 4/15/2014 1:27:54 PM

Answer:	170 CY of embankment should be included in the cost of the rubble rip-rap pay item.	Status: ANSWER PUBLISHED
		Posted: 4/18/2014 10:48:44 AM
Question:	6864: Cannot identify the presence of unsuitable/organic material in the east pond on the plans as stated on sheet 25, pay item notes 550-10-220. Could you please provide us with the quantity of unsuitable and the length of the fence posts so that we can include in the Fence pay item?	Posted: 4/15/2014 1:43:53 PM
Answer:	Contractors shall bid the installation of the fence in accordance with standard index 802 with standard length posts.	Status: ANSWER PUBLISHED
		Posted: 4/15/2014 3:41:26 PM
Question:	6877: What about part 1 of question 6864? How much unsuitable material should we include in this item as stated in the pay item notes, we cannot identify this quantity from the plans provided.	Posted: 4/16/2014 10:49:47 AM
Answer:	As noted in the response to question 6864, it is not the intent of the Department to have the Contractor consider additional length fence posts for unsuitable material and to install the fencing with standard length posts.	Status: ANSWER PUBLISHED
		Posted: 4/16/2014 11:56:53 AM
Question:	6880: Could you please provide a riprap detail with thickness, bedding stone, filter fabric, etc.? The details on the plans do not specify these necessary items.	Posted: 4/17/2014 7:51:37 AM
Answer:	The specifications detail the placement of riprap including thickness, bedding stone etc.	Status: ANSWER PUBLISHED
		Posted: 4/18/2014 10:55:00 AM
Question:	6884: Please clarify the "FH" dimensions provided on Sheet T-21 for Pole #'s A1 and A4	Posted: 4/17/2014 9:29:31 AM
Answer:	The FH dimension has been verified as 0.75 inch as shown on the plan sheet T-21	Status: ANSWER PUBLISHED
		Posted: 4/22/2014 10:25:30 AM
Question:	6885: Pay item note 630-2-11 on Sheet T-5 of the Signalization plans seems to be indicating that all of the underground conduit is to be HDPE. Please clarify if the use of schedule 40 PVC conduit is permitted for use with the exception of the items noted for directional bores and the fiber optic network conduit system.	Posted: 4/17/2014 10:19:42 AM

Answer:	The pay item notes for 630-2-11 and 630-2-12 are not intended to restrict the signal conduit material only to HDPE. The pay item notes for 630-2-11 and 630-2-12 are restricting the SDR to 11, if HDPE conduit is used for signal conduit that is not part of the fiber optic network. The acceptable conduit material type is governed by the current FDOT Standard Specifications for Road & Bridge Construction and FDOT standard index 17736.	Status: ANSWER PUBLISHED
		Posted: 4/22/2014 9:27:43 AM
Question:	6948: What socket type is to be used for the irrigation mainline, Bell end solvent weld or Gasketed?	Posted: 4/22/2014 9:21:59 AM
Answer:	Bell End, Solvent Weld Pipe	Status: ANSWER PUBLISHED
		Posted: 4/23/2014 10:54:39 AM
Question:	6952: Pay Item note(sh#25)102-1 calls out approx. 9,857sy of Temp Pavement for the project, but, there is no note found that describes the temp pavement composition, i.e., 2" asphalt on 6" Limerock base, for instance. What composition of temp pavement is to be provided for this project?	Posted: 4/22/2014 11:14:18 AM
Answer:	Temporary Pavement thickness are shown on sheets 245 and 246. Also, see note 9 on sheet 242.	Status: ANSWER PUBLISHED
		Posted: 4/23/2014 10:20:26 AM
Question:	6977: The "Optional Materials Table" for Drainage Pipe only lists RCP as an acceptable material. Both HDPE Class II and Polypropylene Pipe are now approved for 100 year DSL applications. We are asking for both HDPE Class II and Polypropylene Pipe to be allowed / included as an optional pipe material (as long as min/max cover requirements are met)so that the contractor community can bid accordingly.	Posted: 4/22/2014 4:16:50 PM
Answer:	The County has requested RCP only based on problems with alternate materials.	Status: ANSWER PUBLISHED
		Posted: 4/25/2014 1:10:26 PM
Question:	7020: In the striping plans on sheet S-2 it shows there being bike messages and arrows under the preformed pavement item. It also shows other messages and arrows under that item instead of regular thermoplastic. Is this suppose to be correct?	Posted: 4/24/2014 9:54:29 AM

---

Answer: Yes, the pay items are correct as shown in the plans.

Status: ANSWER PUBLISHED

Posted: 4/25/2014 9:28:18 AM