



Bid Questions and Answers Report

Date & Time:

12/5/2014 12:03:39 PM

District Address: District 2 Construction Office, located at 1109 South Marion Avenue, Lake City, FL 32025

District Phone: (386) 961-7532

Proposal: T2560

Project: 430546-1-52-01

Letting Date: 12/3/2014

Location: CENTRAL OFFICE

Description: SR 10 (ATLANTIC BLVD)

Question:	8676: The Pay Item Footnote 121-70 & the 2nd sentence of 430-175-118 & 124 directs the use of excavatable flowable fill backfill for the new storm drain pipe work. We understand this to mean that whatever volume of pipe trench is excavated, that entire volume will be backfilled only with excavatable flow fill; that no other typically acceptable backfill material is to be used. If other than this understanding, pls advise.	Posted:	11/26/2014 8:34:13 AM
-----------	---	---------	-----------------------

Answer:	If the contractors means and methods will allow him to use another acceptable backfill material and open the travel lanes back to traffic at the end of the allowable work period, then that method would be acceptable in place in flowable fill backfill.	Status:	ANSWER PUBLISHED
		Posted:	11/26/2014 11:37:23 AM