



Bid Questions and Answers Report

Date & Time:

6/19/2014 1:43:25 PM

District Address: District 2 Construction Office, located at 1109 South Marion Avenue, Lake City, FL 32025

District Phone: (386) 961-7532

Proposal: T2534

Project: 210712-3-52-01

Letting Date: 6/18/2014

Location: CENTRAL OFFICE

Description: SR 200

Question: 7260: Upon the receipt of the CAD files for this project, I noticed that the files for the existing ground elevations are missing. The files I'm looking for are GDTMRD01.dgn and GCTRRD01.dgn. They are from Ghiotto in a separate folder either in the roadway or survey folder and were probably overlooked during the creation of the bid documents. Can you provide these file to us? Posted: 5/21/2014 6:13:19 PM

Answer: See Amendment 1. Status: ANSWER PUBLISHED
Posted: 5/28/2014 3:51:38 PM

Question: 7397: Will you please publish a copy of the computation book for this project. Posted: 6/6/2014 10:09:10 AM

Answer: The comp book is posted to the CPP Online Ordering site. Status: ANSWER PUBLISHED
Posted: 6/12/2014 8:53:10 AM

Question: 7398: Please provide information regarding train traffic at the site. Freight / Passenger and daily traffic usage information. Posted: 6/6/2014 10:10:43 AM

Answer: Number of trains - 6 trains/day; Train Speed - 25 MPH; Freight Trains Only - No Passenger Trains Status: ANSWER PUBLISHED
Posted: 6/10/2014 8:35:56 AM

Question: 7405: On Sheet U-16, Sta +/- 176+05, approx 57'Rt, there is a call out for a 12" Tapping Sleeve. There does not appear to be a tapping valve with the sleeve, and we are not sure what this is connecting to. Please provide clarification. Thanks. Posted: 6/6/2014 1:26:18 PM

Answer: The tapping sleeve at this location will not connect to anything new. It is being used to cut off an uninterrupted water main so it can be removed. The tapping sleeve includes a valve so that the flow could be turned off prior to installing a line stop, cap and thrust block.

Status: ANSWER PUBLISHED

Posted: 6/11/2014 3:14:49 PM

Question: 7406: For Fin # 210712-3-56-01 (JEA Utility Plans), please provide the type of pipe material (i.e. PVC or DIP) that is being removed or is being connected to. Thanks.

Posted: 6/6/2014 1:29:09 PM

Answer: Based on existing As-Built information and Subsurface Utility Excavation (SUE) information obtained for the project, the existing force main and water main are PVC.

Status: ANSWER PUBLISHED

Posted: 6/11/2014 2:38:50 PM

Question: 7456: T-1000-17 Measurement and Payment
The Table A -Schedule of Values - REV01 shall be provided to the Contracts Administration Office with the bid.
Can this Excel spreadsheet be e-mailed at bid time to Contracts Administration and if so to what web address?

Posted: 6/11/2014 3:40:52 PM

Answer: The Table A - Schedule of Values should be attached to the bid.

Status: ANSWER PUBLISHED

Posted: 6/12/2014 8:42:31 AM