



Bid Questions and Answers Report

Date & Time: 8/26/2015 10:49:37 AM

District Address: District 1 Construction Office, located at 801 N Broadway, Bartow, FL 33830

District Phone: (863) 519-2222

Proposal: T1623  
Project: 431278-1-52-01  
Letting Date: 8/26/2015  
Location: CENTRAL OFFICE  
Description: SR 35/SR 555 (US 17)

Question:	11357: Plan sheet 5 & 6 show typical sections for structural course with no reference of PG 76-22 PMA. Summary of Quantities sheet SQ-23 thru 26 for this same structural course of asphalt states PG 76-22 PMA. Which one is correct?	Posted:	8/13/2015 3:33:20 PM
Answer:	PG 76-22 PMA shall be used for the structural course as shown on the Summary of Quantities sheet SQ-23 thru SQ-26.	Status:	ANSWER PUBLISHED
		Posted:	8/19/2015 9:56:33 AM
Question:	11360: Special provisions page 29, EXCAVATION - IDENTIFIED AREAS OF CONTAMINATION, 120-1.3 Identified Areas of Contamination states that The contamination type and levels, when known, are in the specifications or in a contamination assessment report posted on the Department's website at the following URL address: <a href="ftp://ftp.dot.state.fl.us/permitsandorutilityworkschedules/">ftp://ftp.dot.state.fl.us/permitsandorutilityworkschedules/</a> . There is no contamination assessment report posted on this URL. Please provide.	Posted:	8/17/2015 10:59:30 AM
Answer:	Contamination testing was performed and did not reveal the presence of contamination. There is no known contamination on this project. The contamination assessment report has been posted to the Department's website at the following URL address: <a href="ftp://ftp.dot.state.fl.us/permitsandorutilityworkschedules/">ftp://ftp.dot.state.fl.us/permitsandorutilityworkschedules/</a> .	Status:	ANSWER PUBLISHED
		Posted:	8/19/2015 6:43:30 AM
Question:	11364: Plan sheets 68 to 71 show potential contamination level 2 testing required. Is the contractor required to perform contamination testing, cleanup, etc. for this project?	Posted:	8/17/2015 3:59:41 PM

---

Answer: The FDOT District Contamination and Remediation contractor performed testing of the areas noted with potential contamination. This testing did not reveal the presence of contamination and there are no expected contamination issues on this project. If unanticipated contamination issues are discovered during construction, they will be handled by the FDOT District Contamination and Remediation contractor.

Status: ANSWER PUBLISHED

Posted: 8/19/2015 6:45:11 AM

---

Question: 11378: The summary of QTYs indicate the curb ramps are all 6" thick, is this correct?

Posted: 8/19/2015 5:06:11 PM

---

Answer: Yes.

Status: ANSWER PUBLISHED

Posted: 8/20/2015 8:11:22 AM