



Bid Questions and Answers Report

Date & Time: 8/26/2015 10:51:01 AM

District Address: District 1 Construction Office, located at 801 N Broadway, Bartow, FL 33830

District Phone: (863) 519-2222

Proposal: T1630

Project: 431319-1-52-01

Letting Date: 8/26/2015

Location: CENTRAL OFFICE

Description: SR 17 (SE LAKEVIEW) FROM US 27/98 TO KENILWORTH BLVD

Question:	11316: Based on the earthwork cross-sections, during phase 1 of construction there will be several places with drop off conditions exceeding 5" and inside of 3' from the travel lanes. The MOT plans only calls for type II barricades or drums. How does the FDOT expect the drop off areas to be handled?	Posted:	8/10/2015 1:32:39 PM
Answer:	The intent is to utilize Note 6 of the Design Standards (Index 600) for Drop Off Conditions (See Sheet 10 of 13), and restore to a minimum 1:4 backslope in each days operation to eliminate the drop off hazards.	Status:	ANSWER PUBLISHED
		Posted:	8/12/2015 9:33:51 AM
Question:	11377: Can the comp book for this project be provided?	Posted:	8/19/2015 11:49:42 AM
Answer:	There is no comp book for each project. All the quantities and pay items for all three projects can be found on the summary of quantity sheets of each project.	Status:	ANSWER PUBLISHED
		Posted:	8/19/2015 5:14:53 PM