



Bid Questions and Answers Report

Date & Time:

5/21/2015 4:02:13 PM

District Address: District 4 Construction Office, located at 3400 West Commercial Blvd. Fort Lauderdale, FL 33309

District Phone: (954) 777-4130

Proposal: T4417

Project: 434007-1-52-01

Letting Date: 5/20/2015

Location: CENTRAL OFFICE

Description: SR 809 (MILITARY TRAIL)

---

Question: 10256: On Sheet L-11, Pole Data & Legend: The single arm 250 watts high pressure sodium luminaire includes a note that the "symbol includes required 9 ft drilled shaft foundation".

Posted: 5/8/2015 3:15:18 PM

Is it the intent of the Department that these light pole foundations are drilled shaft, cast in place foundation or is it the intent that these foundations are drilled shaft, precast foundations?

---

Answer: The foundation should be either precast or cast in place as shown in the standard index 17515. It is up to the contractor to decide whichever method to use.

Status: ANSWER PUBLISHED

Posted: 5/12/2015 7:52:57 AM