



Bid Questions and Answers Report

Date & Time: 10/28/2015 10:34:46 AM

District Address: District 2 Construction Office, located at 1109 South Marion Avenue, Lake City, FL 32025

District Phone: (386) 961-7532

Proposal: T2601

Project: 211663-1-52-01

Letting Date: 10/28/2015

Location: CENTRAL OFFICE

Description: CR 241

---

Question: 12053: Who is the CEI on this project? This information will affect the pricing. Posted: 10/9/2015 2:13:08 PM

---

Answer: Construction oversight will be performed by FDOT using inspection forces from a Continuing Services contract. Status: ANSWER PUBLISHED

Posted: 10/13/2015 7:08:10 AM

---

Question: 12081: Who pays for the embedded data collectors (EDC)? Posted: 10/13/2015 3:17:51 PM

---

Answer: it is included in the cost of the pile. Status: ANSWER PUBLISHED

Posted: 10/14/2015 9:41:21 AM

---

Question: 12082: In regards to Pay Items 0455-34-105 and 0455-34-205, it would be up to the Contractor to choose which option best fits his means and methods. Is this correct? Posted: 10/13/2015 3:29:31 PM

---

Answer: Yes. Contractors must bid only on one alternate. If a contractor bids on both alternates, even if one is 0.00, the system indicates that the bid has errors. Status: ANSWER PUBLISHED

Posted: 10/14/2015 2:32:45 PM

---

Question: 12083: Who is responsible for the testing of the proposed pile installation? Posted: 10/13/2015 3:33:21 PM

---

Answer: See FDOT Specification 455. Status: ANSWER PUBLISHED

Posted: 10/14/2015 1:42:24 PM

---

Question: 12147: Based on the cross sections and MSE wall drawings, it appears that a portion of the MSE backfill lies below the Design high water elevation, 100 yr flood elevation and estimated seasonal high water elevation. Will this backfill volume require the use of coarse aggregate (per spec)? And is there any restriction on the aggregate source material type? Posted: 10/20/2015 4:51:32 PM

---

Answer: Coarse aggregate is required per FDOT Specification 548. Section 548-2.6 covers the coarse aggregate material requirements. Status: ANSWER PUBLISHED  
Posted: 10/23/2015 8:20:27 AM

---

Question: 12179: Optional Base under the approach slab is paid for under which item? Posted: 10/21/2015 3:49:24 PM

---

Answer: The optional base group number for the approach slab can be located on Plan Sheet SQ-5. Status: ANSWER PUBLISHED  
Posted: 10/23/2015 7:25:50 AM

---

Question: 12180: What is the Optional Base # under the approach slab? Posted: 10/21/2015 3:50:32 PM

---

Answer: The optional base group number for the approach slab can be located on Plan Sheet SQ-5. Status: ANSWER PUBLISHED  
Posted: 10/23/2015 7:26:29 AM

---

Question: 12181: Is Class V finish required? Posted: 10/21/2015 3:50:54 PM

---

Answer: A class V finish is not required. Status: ANSWER PUBLISHED  
Posted: 10/23/2015 8:18:29 AM