

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: CT150826 Call Order: 010 Proposal: T3403 District:03  
 Counties: ESCAMBIA  
 Road Name: SR 95 (US 29)  
 Limits: FROM N OF CHAMPION DRIVE TO ALABAMA STATE LINE  
 Project(s): 42692915201(\*) Federal Aid No: 0091058P  
 Total Roadway Length: 15.366 Miles Contract Days: 100  
 Total Bridge Length: 0.068 Miles Letting Date: 08/26/15  
 Total Proposal Length: 15.434 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Days (Acq. Time)

Proposal Budget Estimate: \$830,905.00

Please read the full advertisement

**Description:**

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <http://www.dot.state.fl.us/equalopportunityoffice/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <http://www.dot.state.fl.us/cc-admin/forms/forms.shtm>  
 It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: [fdot.bdi@dot.state.fl.us](mailto:fdot.bdi@dot.state.fl.us).

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid.

If bidding through Bid Express, please upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: <http://www.dot.state.fl.us/equalopportunityoffice/bdi.shtm>

Bid Bonds of \$500 are required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

A Performance Bond is not required for contracts \$250,000.00 and less.

The improvements under this contract consist of safety improvements to SR 95 (US 29), that include guardrail upgrades (including bridges 480012, 480013, 480177 and 480178), sidewalk replacement and signalized pedestrian crossings.

**Call Order: 010 Proposal: T3403**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ROADWAY</b>				
	0101- 1-	MOBILIZATION (42692915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42692915201)	DA	100.000
	0102- 60-	WORK ZONE SIGN	ED	18,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,500.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	200.000

**Call Order: 010 Proposal: T3403**

ALT	Item	Description	Unit	Quantity
	0102- 74- 5	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	910.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	7,000.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	40.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	80.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	80.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,567.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	63.000
	0107- 1-	LITTER REMOVAL	AC	606.950
	0107- 2-	MOWING	AC	606.950
	0110- 1- 1	CLEARING & GRUBBING (42692915201)	AC	2.540
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	693.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (42692915201)	LS	1.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	9,343.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	280.200
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	1.000
	0425- 10-	YARD DRAIN	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	84.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	7.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	220.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	410.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,829.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	33.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	492.000
	0527- 2-	DETECTABLE WARNINGS	SF	962.000
	0536- 1- 1	GUARDRAIL -ROADWAY	LF	4,563.000
	0536- 8-	GUARDRAIL- BRIDGE ANCHORAGE ASSEMBLY, FURNISH & INSTALL	EA	10.000
	0536- 8- 6	GUARDRAIL, BRIDGE ANCHORAGE ASSEMBLY, REMOVE	EA	10.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,496.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY- FLARED	EA	20.000
	0536- 85- 25	GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE II	EA	13.000
	0538- 1-	GUARDRAIL RESET	LF	3,563.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	10,320.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42692915201)	LS	1.000
<b>Section 0002 SIGNING</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	4.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	30.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	28.000
	0700- 2- 50	MULTI- POST SIGN, F&I GROUND MOUNT, RELOCATE	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42692915201)	LS	1.000
<b>Section 0003 SIGNALIZATION</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	19.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000

**Call Order: 010 Proposal: T3403**

ALT	Item	Description	Unit	Quantity
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	2.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	3.000