Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT151028 Call Order: 013 Proposal: T5542 District:05

Counties: VOLUSIA

Road Name: SR 400 (I-4)

Limits: FROM THE EAST ABUTMENT OF THE ST. JOHNS RIVER BRIDGE TO VARIOUS POINTS AROUND SAXON BLVD

Project(s): 43245515201(*) Federal Aid No: 0042270I

Total Roadway Length:	5.287 Miles	Contract Days:	260
Total Bridge Length:	0.091 Miles	Letting Date:	10/28/15
Total Proposal Length:	5.378 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60 DAYS

Proposal Budget Estimate: $7,829,176.00

Please read the full advertisement

Description: Lump Sum

The improvements under this contract consist of resurface, restore and rehabilitate (RRR) SR 400 (I-4) from the east abutment of the St. Johns River Bridge (MP 0.486) to the eastbound pavement joint 0.5 miles south of Saxon Blvd. (MP 5.886) and to the westbound pavement joint 0.9 miles south of Saxon Blvd. (MP 5.482). From MP 4.61 to 4.64 eastbound – reconstruct 80 ft of the outside shoulder and construct 800 SY of miscellaneous asphalt pavement between the shoulder and existing Enterprise Rd. overpass abutment wall. From MP 4.65 to 4.63 westbound - reconstruct 80 ft of the outside shoulder and construct approximately 340 SY of miscellaneous asphalt pavement between the shoulder and existing Enterprise Rd. overpass abutment wall ramp milling and resurfacing limits are listed as follows: Ramp 004 westbound I-4 exit ramp to Dirksen Rd.; Ramp 005 westbound I-4 entrance ramp from Dirksen Rd.; Ramp 006 eastbound I-4 exit ramp to Dirksen Rd.; Ramp 007 eastbound I-4 entrance ramp from Dirksen Rd.

Call Order: 013 Proposal: T5542

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0999- 2-	LUMP SUM CONTRACT, ALTERNATIVE BIDDING (43245515201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43245515201)	LS	1.000