



Bid Questions and Answers Report

Date & Time:

1/27/2016 9:02:35 AM

District Address: District 1 Construction Office, located at 801 N Broadway, Bartow, FL 33830

District Phone: (863) 519-2222

Proposal: T1628

Project: 430119-1-52-01

Letting Date: 1/27/2016

Location: CENTRAL OFFICE

Description: SR 78 (BAYSHORE RD)

---

Question: 12880: Plan sheet 36 states that the water flow for the culvert shall be maintained at all times. Is by pass pumping through the culvert allowed, or is the department allowing longitudinal construction joints? Posted: 1/12/2016 3:53:14 PM

---

Answer: Yes, water flow for the culvert shall be maintained at all times as stated on Plan Sheet 36. All bypass pumping shall be at the mean's and methods of the contractor during construction to maintain proper water flow. The contractor shall refer to the permit requirements for this project. Please refer to the Standard Index 289 drawings ("Typical Section Thru Multiple Barrel Culvert") that only horizontal construction joints are permitted. Status: ANSWER PUBLISHED  
Posted: 1/14/2016 2:00:29 PM

---

Question: 12906: I do not see Pay-Items for Temporary Signalization and Maintenance & Temporary Detection and Maintenance; why were they not added to the Bid Solicitation? Posted: 1/14/2016 1:30:09 PM

Both pay items are required for projects that have signalized intersections within the project limits. Please see FDOT ESTIMATES BULLETIN 14-03 for details.

Additionally please add Pay-Items 102-104 and 102-107-1 for the full duration of the contract and for the total number of intersections within the project limits.

---

Answer: The pay items were added to the plans and sent out to all prospective bidders as Addendum #2, Amendment #2 dated 1/28/2016. Status: ANSWER PUBLISHED  
Posted: 1/20/2016 4:49:29 PM

---

Question: 12909: Will the department consider extending the 90 day acquisition time to accommodate the lead time for the amount of signal work on this project? In order to get shop drawings submitted and approved and mast arms fabricated to allow for proper sequencing of activities on a project of this magnitude, 140 to 160 days seems to be more in line with previous FDOT projects. Posted: 1/14/2016 2:19:02 PM

---

Answer: Contractor's shall prepare their bids based upon the original time frame as shown within the Department's Advertisement. If after the letting the contractor can provide ample justification to do so, the Department may extend the acquisition time to accommodate the lead time for the signal equipment items.

Status: ANSWER PUBLISHED

Posted: 1/14/2016 4:25:29 PM

---

Question: 13006: Please verify the bid quantities for Pay Item 630-2-11. My take-off quantities for this Pay Item, as identified on plan sheets T-5 through T-8, do not match the Summary of Quantities on plan sheet T-2 and Bid Solicitation.

Posted: 1/20/2016 3:37:35 PM

---

Answer: All prospective bidders shall prepare their bids for the underground conduit quantities 630-2-11 as shown the Tabulation of Quantities (T-2) Sheet T-2 of 846 LF and the Bid Solicitation.

Status: ANSWER PUBLISHED

Posted: 1/21/2016 4:03:50 PM

---

Question: 13031: How is the disconnecting, removal, reinstall and splicing of the existing ATMS Fiber being paid for. Why are there no pay-items to cover these items of work; see plan sheet T-6, bottom right-hand.

Posted: 1/22/2016 9:36:41 AM

---

Answer: Questions posted to this site before 5:00 P.M. (EST) on the seventh calendar day prior to the bid opening, or tenth day prior to the December bid opening will be responded to by the Department. For Questions posted after these times, an answer cannot be assured.

Status: ANSWER PUBLISHED

Posted: 1/25/2016 3:26:51 AM