



Bid Questions and Answers Report

Date & Time: 7/27/2016 8:08:46 AM

District Address: District 5 Construction Office, located at 719 South Woodland Blvd, Deland, FL 32720

District Phone: (386) 943-5350

Proposal: T5566

Project: 432437-1-52-01

Letting Date: 7/27/2016

Location: CENTRAL OFFICE

Description: SR 5 (US 1)

| | | | |
|-----------|--|---------|----------------------|
| Question: | 15124: Will pre-milling of the shoulders adjacent 4.25" milling be permitted to allow positive drainage? If not, please provide phasing plan for resurfacing R2 and adjacent shoulder. | Posted: | 7/8/2016 8:56:11 AM |
| Answer: | Bid Question Response #15124: Yes. Pre-milling of the shoulders adjacent to the 4.25" milling in the outside lane is permitted | Status: | ANSWER PUBLISHED |
| | | Posted: | 7/20/2016 5:54:30 PM |
| Question: | 15205: Many of the existing crossovers hold water after light rain. Please advise. | Posted: | 7/18/2016 2:48:49 PM |
| Answer: | Bid Question Response #15205: The bidder is not clear on the question asked. The median portions are shown to be milled and resurfaced as part of this contract. | Status: | ANSWER PUBLISHED |
| | | Posted: | 7/22/2016 1:21:05 PM |
| Question: | 15206: Who is responsible for the benches and signage for the existing and proposed bus stops? | Posted: | 7/18/2016 2:54:41 PM |
| Answer: | Bid Question Response #15206: Per note on sheet S-5 the contractor is to coordinate with Space Coast Area Transit Authority for the locations of the signs and benches. | Status: | ANSWER PUBLISHED |
| | | Posted: | 7/22/2016 1:21:43 PM |
| Question: | 15207: There is a Memorial Marker in the project limits. What is the responsibility of the Contractor with regards to the Memorial? | Posted: | 7/18/2016 2:58:38 PM |
| Answer: | Bid Question Response #15207: The contractor is not obligated to relocate or replace the marker. The Department reserves the right to have the memorial marker removed due to any construction or other maintenance needs. | Status: | ANSWER PUBLISHED |
| | | Posted: | 7/20/2016 6:03:33 PM |

| | | | |
|-----------|---|---------|-----------------------|
| Question: | 15208: What is the depth and reinforcement of the proposed concrete removal? The coring data does not show it. | Posted: | 7/18/2016 3:14:47 PM |
| Answer: | Bid Question Response #15208: The quantity shown in the plans is based on a SY measurement per direction from the Basis of Estimates Manual and FDOT Standard Specification 110. | Status: | ANSWER PUBLISHED |
| | | Posted: | 7/22/2016 1:22:16 PM |
| Question: | 15213: Please provide additional details regarding the widening near the gopher tortoise burrows. The 25 foot buffer is too close to the adjacent work area. Please advise. | Posted: | 7/18/2016 4:59:21 PM |
| Answer: | Bid Question Response #15213: Per project note 12, on plan sheet 11, Gopher tortoise burrows were identified within the project corridor near station 920+60 (RT) and 921+25 (RT). The Contractor shall avoid the use of heavy equipment within 25 feet of the burrow entrances and minimize the soil disturbance at the 25-foot buffer edge to the greatest extent possible. | Status: | ANSWER PUBLISHED |
| | | Posted: | 7/22/2016 1:23:03 PM |
| Question: | 15221: Will the Department accept 4.00" of Type B-12.5 in lieu of Type B Stabilization under the Optional Base Group 06 (5.00" Asphalt Option)? | Posted: | 7/20/2016 12:30:53 PM |
| Answer: | Bid Question Response #15221: Per specification 160-2.4, the Department allows, at no additional cost, the substitution of 6 inches of granular subbase meeting the requirements of specification 290-2 and 290-3, when 12 inches of stabilization requiring a limerock bearing ratio (LBR) value of 40 is specified. | Status: | ANSWER PUBLISHED |
| | | Posted: | 7/22/2016 1:23:34 PM |
| Question: | 15233: Please clarify where the 5' Lawn Should is paid. | Posted: | 7/22/2016 2:19:37 PM |
| Answer: | Questions posted to this site before 5:00 P.M. (EST) on the seventh calendar day prior to the bid opening, or tenth day prior to the December bid opening will be responded to by the Department. For Questions posted after these times, an answer cannot be assured. | Status: | ANSWER PUBLISHED |
| | | Posted: | 7/25/2016 3:27:04 AM |
| Question: | 15234: Please clarify where the 5' Lawn Shoulder is paid. | Posted: | 7/22/2016 2:21:12 PM |
| Answer: | Questions posted to this site before 5:00 P.M. (EST) on the seventh calendar day prior to the bid opening, or tenth day prior to the December bid opening will be responded to by the Department. For Questions posted after these times, an answer cannot be assured. | Status: | ANSWER PUBLISHED |
| | | Posted: | 7/25/2016 3:27:04 AM |