



Bid Questions and Answers Report

Date & Time: 6/15/2016 9:09:37 AM

District Address: District 2 Construction Office, located at 1109 South Marion Avenue, Lake City, FL 32025

District Phone: (386) 961-7532

Proposal: T2623

Project: 427474-2-52-01

Letting Date: 6/15/2016

Location: CENTRAL OFFICE

Description: SR 93 (I-75)

Question: 14766: In reference to the DMS (Dynamic Message Signs) to be installed on this project, can you please confirm the # of lines, # of characters per line, character height, pixel pitch and character font size? In addition, are the DMS to be full color or monochrome amber? Posted: 6/1/2016 9:25:44 AM

Answer: Per the pay item 700-9-137, Walk-In DMS, F&I-W/ UPS Full Color, the DMS shall be full color. The DMS shall be capable of displaying three (3) lines of 21 characters (18" Height) per line using a 14x8 font, with a pixel pitch of 34mm or better. Status: ANSWER PUBLISHED
Posted: 6/7/2016 3:51:17 PM

Question: 14800: In review of the bid documents, 15 days of acquisition time does not seem adequate. The materials required for this project are not readily accessible and are subject to a lengthy submittal / review process. Because many of these items will not be immediately available for installation the initial contract time could be unproductive. We ask that the department consider increasing the acquisition time to 90 days. Posted: 6/2/2016 8:57:42 AM

Answer: The acquisition time remains at 15 days. Status: ANSWER PUBLISHED
Posted: 6/3/2016 9:09:22 AM

Question: 14853: Because the composite cable also includes fiber optic cable, are the fiber connections and terminations inclusive of this pay item, since this is normally a pay item for copper communications cabling. Posted: 6/3/2016 1:07:50 PM

Answer:	Per the Technical Special Provision T633, section T633-2.1, Pay Item 633-8-1 shall include the connectors to interface with respective devices as shown in the plans which includes the complete termination of all fiber strands at both ends of the cable. Pay Item 633-8-1 Multi-Conductor Communications Cables that include fiber optic strands shall include the mechanical splice termination of ST connectors and the ST connectors, for all fibers at both ends of the cables. Buffer tube fan out kits, which are only necessary if tight buffer tube fibers are not used in the composite cable, are also incidental to this pay item if needed. This pay item also includes the termination of all power and copper communication wires with the corresponding connectors.	Status:	ANSWER PUBLISHED
		Posted:	6/6/2016 11:23:03 AM