Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT160831 Call Order: 013 Proposal: T4438 District:04

Counties: PALM BEACH

Road Name: SR 809 (MILITARY TRAIL)

Limits: FROM S OF SR 802 (LAKE WORTH RD) NORTHERLY 3.391 MILES TO S OF SR 80 (SOUTHERN BLVD)

Project(s): 42871915201(*) Federal Aid No: 6319016U

Project(s): 42871915202 Federal Aid No: 6319016U

Project(s): 42871915203 Federal Aid No: N/A

Total Roadway Length:	3.931 Miles	Contract Days:	414
Total Bridge Length:	0.000 Miles	Letting Date:	08/31/16
Total Proposal Length:	3.931 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120 Calendar Days

Proposal Budget Estimate: $8,130,132.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, replacing pavers with concrete, pavement regrading, utility adjustments and drainage improvements, signing and pavement markings, signalization, pedestrian detectors, traffic monitoring sites, intelligent transportation systems including dynamic message signs and fiber optic with ADMS, MVDS, CCTV, and Trailblazer Sites along SR809 (Military Trail).

Call Order: 008 Proposal: T4438

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (42871915201)	LS	1.000
	0101- 1-	MOBILIZATION (42871915202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42871915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42871915202)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	MH	512.000
	0102- 60-	WORK ZONE SIGN	ED	101,016.000
	0102- 61-	BUSINESS SIGN	EA	14.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,700.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,656.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	828.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	5,136.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,898.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,898.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,880.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	117.000
	0107- 1-	LITTER REMOVAL	AC	196.820
	0107- 2-	MOWING	AC	16.630
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (42871915201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (42871915201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	397.000

ALT	Item	Description	Unit	Quantity
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	507.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	3,222.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	43,519.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	167,949.000
	0327- 70- 10	MILLING EXIST ASPH PAVT, 5" AVG DEPTH	SY	3,086.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	96.900
	0337- 7- 74	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76 -22, ARB	TN	18,754.800
	0425- 1-211	INLETS, CURB, TYPE 10, <10'	EA	1.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	67.000
	0425- 6-	VALVE BOXES, ADJUST	EA	2.000
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	14.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	140.000
	0430-175-215	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 15"S/CD	LF	10.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	47.000
	0431- 1- 1	PIPE LINER, OPTIONAL MATERIAL, 0-24"	LF	740.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	464.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,761.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	660.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	6.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,306.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,579.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,473.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	507.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	9.796
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	8,471.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	7,133.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	14.165
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	95.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	256.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.380
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42871915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42871915202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42871915203)	LS	1.000
	1050- 11-414	UTILITY PIPE, F&I, DI/CI, CASING/CONDUIT, 8 - 19.9"	LF	12.000
	1050- 11-424	UTILITY PIPE, F&I, DI/CI, WATER / SEWER, 8 - 19.9"	LF	120.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	112.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	25.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	10.000

ALT	Item	Description	Unit	Quantity
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	128.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	4.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0705- 11- 4	DELINEATOR, FLEXIBLE HIGH PERFORMANCE 48"	EA	48.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (42871915201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	8,471.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	7,133.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.920
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	6.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.327
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	95.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROWS	EA	258.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	9.768
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.629
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	14.137
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.366
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	465.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,270.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	7.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	49.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	18.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	11.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	9.000
	0649- 31-203	MAST ARM,F&I, WIND SPEED-130,SINGLE ARM,W/0 LUMINAIRE-60	EA	1.000
	0649- 36-300	MAST ARM, REMOVE SHALLOW FOUNDATION, BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 14	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	3.000
	0650- 1- 16	TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0650- 1- 60	TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000
	0650- 1- 70	TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	32.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	2.000

ALT	Item	Description	Unit	Quantity
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	23.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	96.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	24.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	24.000
	0660- 4- 42	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE ABOVE GROUND EQUIPMENT	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	36.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	8.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	9.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	7.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	12.000
	0695- 6- 12	TRAFFIC MONOTORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	1.000
Section 0006 Intelligent Transportation System				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	455.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	7,927.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	10,620.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	72.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	10.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	10.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	18.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	1,341.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	36.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	41.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	12.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	3,553.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	16.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	16.000
	0641- 2- 15	PRESTRESSED CONCRETE POLE, F&I, TYPE P-V	EA	5.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	6.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	6.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	4.000
	0676- 2-142	ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	10.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	4.000

ALT	Item	Description	Unit	Quantity
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0682- 1-153	ITS CCTV CAMERA, F&I, STATIONARY, IP, HIGH DEFINITION	EA	4.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	18.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	14.000
	0685-501-	SYSTEM AUXILIARIES, ITS DEVICE MANAGEMENT SOFTWARE FOR PROJECT 428719-1-52-02 (42871915202)	LS	1.000
	0700- 8-132	FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL-WITH UPS, FULL COLOR, 12-20 SF	EA	14.000
	0700- 8-135	FRONT ACCESS DYNAMIC MESSAGE SIGN, FURNISH & INSTALL-WITH UPS, FULL COLOR, 51-100 SF	EA	4.000
	0700- 10-122	DMS SUPPORT STRUCTURE, CANTILEVER, 21-30 FT	EA	4.000
	0700- 10-130	DMS SUPPORT STRUCTURE, FURNISH & INSTALL, PEDESTAL	EA	9.000