Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT160615 Call Order: 012 Proposal: T1658 District:01

Counties: COLLIER

Road Name: SR 93 (I-75)

Limits: FROM THE WEST TOLL BOOTH TO THE FAKA-UNION CANAL BR

Project(s): 43902815201(*) Federal Aid No: N/A

Total Roadway Length:	9.084 Miles	Contract Days:	175
Total Bridge Length:	0.000 Miles	Letting Date:	06/15/16
Total Proposal Length:	9.084 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	90 Days (Aqui Time)

Proposal Budget Estimate: $5,487,351.00

Please read the full advertisement

Description:

The improvements under this contract consist of fencing on State Road 93 (I-75) from the Faka-Union Canal Bridge westerly 9.084 miles to west of the West Toll Booth, in the City of Naples, Collier County.

Call Order: 012 Proposal: T1658

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43902815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43902815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	7,200.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	10.000
	0107- 1-	LITTER REMOVAL	AC	993.250
	0107- 2-	MOWING	AC	763.520
	0110- 1- 1	CLEARING & GRUBBING (43902815201)	LS	1.000
	0550- 10-251	FENCING, TYPE B, 8.1-10.0', WITH BARBED WIRE ATTMT	LF	96,187.000
	0550- 60-213	FENCE GATE, TYPE B, SINGLE, 12.1-18.0' OPENING	EA	3.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	42,709.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43902815201)	LS	1.000