

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT160330 Call Order: 013 Proposal: T4437 District:04
 Counties: PALM BEACH
 Road Name: SR 9/I-95
 Limits: AT SR 706/INDIANTOWN RD
 Project(s): 43510215201(*) Federal Aid No: N/A
 Total Roadway Length: 0.748 Miles Contract Days: 48
 Total Bridge Length: 0.182 Miles Letting Date: 03/30/16
 Total Proposal Length: 0.930 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 30 Calendar Days

Proposal Budget Estimate: \$582,057.00

Please read the full advertisement

Description:

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <http://www.dot.state.fl.us/equalopportunityoffice/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <http://www.dot.state.fl.us/cc-admin/forms/forms.shtm>
 It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid.

If bidding through Bid Express, please upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: <http://www.dot.state.fl.us/equalopportunityoffice/bdi.shtm>

Bid Bonds of \$500 are required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

A Performance Bond is not required for contracts \$250,000.00 and less.

The improvements under this contract consist of milling and resurfacing, minor widening, high-friction epoxy overlay for concrete bridge decks for Bridge Numbers 930376, 930390, 930385 and 930380, wet pavement sensors and triggered flashing warning beacons (ITS Road Weather Information System), and signing and pavement markings along SR 9 /I-95 SB On-Ramp.

Call Order: 013 Proposal: T4437

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0403- 1- 1	EPOXY CONCRETE OVERLAY FOR CONCRETE BRIDGE DECKS, PROJECT 435102-1-52-01	SY	4,288.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43510215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43510215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	MH	26.000

Call Order: 013 Proposal: T4437

ALT	Item	Description	Unit	Quantity
	0102- 60-	WORK ZONE SIGN	ED	613.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,900.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	126.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	72.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	139.000
	0104- 10- 3	SEDIMENT BARRIER	LF	7,720.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	9.000
	0107- 1-	LITTER REMOVAL	AC	23.250
	0107- 2-	MOWING	AC	8.660
	0110- 1- 1	CLEARING & GRUBBING (43510215201)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43510215201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	354.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	189.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	236.000
	0327- 70- 19	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	SY	8,486.000
	0334- 1- 14	SUPERPAVE ASPHALTIC CONC, TRAFFIC D	TN	18.400
	0337- 7- 22	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22, PMA	TN	365.300
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	189.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43510215201)	LS	1.000
Section 0003 Signing				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	60.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	915.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	10.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870, UP TO 12 SF	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	2.000
	0700- 12- 12	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, TWO BEACONS	AS	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43510215201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	677.000
	0711- 14-124	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 18", FOR DIAGONAL OR CHEVRON ON CONCRETE BRIDGE SURFACE	LF	440.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.455
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.298
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.752
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.746
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	60.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	915.000

Call Order: 013 Proposal: T4437

ALT	Item	Description	Unit	Quantity
	0781- 3-112	ITS ROAD WEATHER INFORMATION SYSTEM, FURNISH & INSTALL, FIELD HARDWARE, MOUNTED TO EXISTING STRUCTURE	EA	1.000