

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: CT161026 Call Order: 010 Proposal: T3601 District:03
 Counties: BAY
 Road Name: ARTHUR DR
 Limits: OVER LYNN HAVEN BAYOU (BRIDGE NO. 464514)
 Project(s): 43046315201(*) Federal Aid No: 00B3214B
 Total Roadway Length: 0.056 Miles Contract Days: 150
 Total Bridge Length: 0.008 Miles Letting Date: 10/26/16
 Total Proposal Length: 0.064 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 15 Calendar Days

Proposal Budget Estimate: \$1,072,432.00

Please read the full advertisement

Description:

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at <http://www.dot.state.fl.us/equalopportunityoffice/bdi.shtm>.

For more information about bidding on BDI projects, please see the training guide located at <http://www.cmdp-bgp.com/bdi-projects.html>

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: <http://www.dot.state.fl.us/cc-admin/forms/forms.shtm>
 It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid.

If bidding through Bid Express, please upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: <http://www.dot.state.fl.us/equalopportunityoffice/bdi.shtm>

Bid Bonds of \$500 are required for bids over \$150,000 and may be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

A Performance Bond is not required for contracts \$250,000.00 and less.

The improvements under this contract consist of replacing bridge No. 464514 over Lynn Haven Bayou on Arthur Dr. Additional work includes paving, guardrail improvements and signing and pavement marking.

Call Order: 010 Proposal: T3601

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43046315201)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	47.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	26.900
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	45.800
	0400- 4- 41	CONCRETE CLASS IV, PRECAST DECK OVERLAY	CY	25.200

Call Order: 010 Proposal: T3601

ALT	Item	Description	Unit	Quantity
	0400- 7-	BRIDGE DECK GROOVING, LESS THAN 8.5"	SY	142.000
	0400-128-	GROUTING PRECAST DECK PANELS, NON-SHRINK GROUT	LF	265.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	4,171.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	2,648.000
	0415- 1- 8	REINFORCING STEEL- BULKHEAD	LB	4,756.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	9,042.000
	0450- 3- 11	PRESTRESSED SLAB UNITS, WIDTH 48", THICKNESS 12"	LF	265.000
	0450- 3- 21	PRESTRESSED SLAB UNITS, WIDTH 60", THICKNESS 12"	LF	44.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	403.000
	0455- 87-	ANCHOR BAR, STEEL	EA	14.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	6,267.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	165.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	55.000
	0521- 5- 1	CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	LF	172.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	28.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	509.200
	0530- 74-	BEDDING STONE	TN	181.300
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43046315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43046315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,250.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	336.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,350.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	84.000
	0104- 10- 3	SEDIMENT BARRIER	LF	716.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	287.000
	0110- 1- 1	CLEARING & GRUBBING (43046315201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	541.000
	0160- 4-	TYPE B STABILIZATION	SY	1,519.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	2,408.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	1,193.000
	0334- 1- 22	SUPERPAVE ASPH CONC, TRAFFIC B, PG76-22, PMA	TN	195.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	8.200
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	194.000
	0536- 8-	GUARDRAIL- BRIDGE ANCHORAGE ASSEMBLY, FURNISH & INSTALL	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	50.000
	0536- 85- 22	GUARDRAIL END ANCHORAGE ASSEMBLY- FLARED	EA	1.000
	0536- 85- 24	GUARDRAIL END ANCHORAGE ASSEMBLY- PARALLEL	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	1,438.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	970.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	3.000

Call Order: 010 Proposal: T3601

ALT	Item	Description	Unit	Quantity
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43046315201)	LS	1.000