BID SOLICITATIONENOTICENANDFAPPROXIMATETQUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 01130418 CALL ORDER: 006 PROPOSAL ID: E1M64 DISTRICT: 01
COUNTIES : POLK , , ,

ROAD NAME : US 27 (SR 25)
LIMITS : FROM N OF SR 540 TO N OF SR 542

FINPROJ NO(S): FEDERAL AID NO(S): MAJOR WORK TYPE:
19770625201 (*) N/A LANDSCAPING

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 100
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 04/18/13
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS:
SPECIAL START DATE: N/A
ACQUIS./FLEXIBLE START TIME : 30 Days (Acq. Time)

PROPOSAL BUDGET ESTIMATE: $ 175,000.00

PROPOSAL PACKAGE FEE(PLANS + PROPOSAL): $0.00 PLANS ONLY FEE: $0.00 SPECS ONLY FEE: $0.00

DESCRIPTION:
The improvements under this Contract consist of Landscaping on State Road 25 from north of State Road 540 northerly approximately 0.807 miles, to north of State Road 542 in the Town of Dundee, Polk County.

ALT	ITEM NO.		D E S C R I P T I O N	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<			SECTION 0001 LANDSCAPE / PERIPHERAL		>>>>>>>>>>>
	0101 1		MOBILIZATION (19770625201)	LS	1.000
	0102 1		MAINTENANCE OF TRAFFIC (19770625201)	LS	1.000
	0102 60		WORK ZONE SIGN	ED	1,020.000
	0102 74	1	TEMPORARY BARRICADE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	19,421.000
	0102 74	2	BARRICADE, TEMPORARY, TYPE III, 6'	ED	20.000
	0102 76		ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	100.000
	0102 77		HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	410.000
	0104 10	3	SEDIMENT BARRIER	LF	1,880.000
	0104 18		INLET PROTECTION SYSTEM	EA	29.000
	0555 1	1	DIRECTIONAL BORE, LESS THAN 6"	LF	965.000
	0555 1	2	DIRECTIONAL BORE, 6" TO < 12"	LF	959.000
	0580 1	1	LANDSCAPE COMPLETE- SMALL PLANTS (19770625201)	LS	1.000
	0580 1	2	LANDSCAPE COMPLETE- LARGE PLANTS (19770625201)	LS	1.000
	0590 70		IRRIGATION SYSTEM (19770625201)	LS	1.000
	0639 1	12	ELECTRICAL POWER SERVICE, OVERHEAD, METER FURNISHED BY CONTRACTOR	AS	2.000
	0999 25		INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000