BID SOLICITATIONENOTICENANDFAPPROXIMATETQUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 01130418 CALL ORDER: 007 PROPOSAL ID: E1M65-R0 DISTRICT: 01
COUNTIES : DIST/ST-WIDE,LEE , CHARLOTTE,

ROAD NAME : FT. MYERS OPERATIONS
LIMITS : MAINTENANCE CONTRACTS

FINPROJ NO(S): FEDERAL AID NO(S): MAJOR WORK TYPE:
43272917204 (*) N/A ROUTINE MAINTENANCE

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 365
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 04/18/13
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS:
SPECIAL START DATE: N/A
ACQUIS./FLEXIBLE START TIME : N/A

PROPOSAL BUDGET ESTIMATE: $ 120,000.00

PROPOSAL PACKAGE FEE(PLANS + PROPOSAL): $0.00 PLANS ONLY FEE: $0.00 SPECS ONLY FEE: $0.00

DESCRIPTION:
The Improvements under this Contract consist of Guardrail Repair and Replacement. Charlotte & Lee

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<		SECTION 0001 GUARDRAIL REPAIR (LF)		>>>>>>>>>>>
	0339 1	MISCELLANEOUS ASPHALT PAVEMENT	TN	40.000
	0536 7	SPECIAL GUARDRAIL POST	EA	20.000
	0536 8	GUARDRAIL- BRIDGE ANCHORAGE ASSEMBLY, FURNISH & INSTALL	EA	6.000
	0536 85 26	GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE CRT	EA	7.000
	0538 1	GUARDRAIL RESET	LF	1,500.000
	E536 3141	GUARDRAIL STANDARD PANEL (REPLACE) (SHOP BENT)	LF	200.000
	E536 3240	GUARDRAIL THRIE BEAM (REPLACE)	LF	50.000
	E536 3540	GUARDRAIL (PIPE RAIL SAFETY) (REPLACE)	LF	50.000
	E536 6 47	END ANCHORAGE ASSEM (REPLACE) (BARRIER WALL)	EA	4.000
	E536 6 61	END ANCHORAGE ASSEM (F&I) (TYPE II)	EA	8.000
	E536 6422	END ANCHORAGE ASSEM (REPLACE) (FLARED)	EA	20.000
	E536 6424	END ANCHORAGE ASSEM (REPLACE) (PARALLEL)	EA	20.000
	E536 12602	GUARDRAIL REPAIRS (REPLACE) (WOOD BLOCK)	EA	150.000
	E536 12605	GUARDRAIL REPAIRS (REPLACE) (STEEL POST IN ASPH.)	EA	150.000
	E536 12606	GUARDRAIL REPAIRS (REPLACE) (STEEL POST IN SOIL)	EA	20.000
	E536 12608	GUARDRAIL REPAIRS (REPLACE) (WOOD POST IN ASPH.)	EA	193.000
	E536 12609	GUARDRAIL REPAIRS (REPLACE) (WOOD POST IN SOIL)	EA	15.000
	E536 12611	GUARDRAIL REPAIRS (REPLACE) (REFLECTORS)	EA	30.000
	E536 12615	GUARDRAIL REPAIRS (REPLACE) (FILLER BLOCKS)	EA	15.000
	E536 12617	GUARDRAIL REPAIRS(REPLACE)(PANEL, 12-1/2')	EA	200.000
	E536301502	END ANCHOR ASSEM TYPE II (REPL ROUND END SECT)	EA	2.000
	E536302503	END ANCHOR ASSEM TYPE IV (REPL BUFFER END SECT)	EA	2.000
	E536302504	END ANCHOR ASSEM TYPE IV (REPL ANCHOR PANEL SECT)	EA	2.000
	E536302505	END ANCHOR ASSEM TYPE IV (REPL CABLE ASSEMBLY)	EA	2.000
	E536302506	END ANCHOR ASSEM TYPE IV (REPL STEEL TUBE & POST)	EA	2.000
	E536302507	END ANCHOR ASSEM TYPE IV (REPL ANCHOR PLATE)	EA	2.000
	E536302508	END ANCHOR ASSEM TYPE IV (REPL TIMBER BREAK POST)	EA	2.000
	E536306501	END ANCHOR ASSEM BRIDGE (REPL SPECIAL END SHOE)	EA	2.000
	E536306503	END ANCHOR ASSEM BRIDGE (REPL TIMBER FILL BLOCK)	EA	2.000
	E536314501	END ANCHOR ASSEM SRT-350/8 (REPL CABLE ASSEMBLY)	EA	2.000
	E536314503	END ANCHOR ASSEM SRT-350/8 (REPL AMBER REFL SHT)	EA	2.000
	E536314504	END ANCHOR ASSEM SRT-350/8 (REPL BEARING PLATE)	EA	2.000
	E536314505	END ANCHOR ASSEM SRT-350/8 (REPL TIMBER BRK POST)	EA	2.000
	E536314509	END ANCHOR ASSEM SRT-350/8 (REPL STRUT/YOKE ASSM)	EA	2.000
	E536314510	END ANCHOR ASSEM SRT-350/8 (REPL TMBR LINE POST)	EA	2.000
	E536314511	END ANCHOR ASSEM SRT-350/8 (REPL GUARDRAIL BEAM)	EA	2.000
	E536322501	END ANCHOR ASSEM FLARED (REPL FLARED END SECT)	EA	2.000
	E536322502	END ANCHOR ASSEM FLARED (REPL ROUND END SECT)	EA	2.000
	E536322503	END ANCHOR ASSEM FLARED (REPL BUFFER END SECT)	EA	2.000