BID SOLICITATIONENOTICENANDFAPPROXIMATETQUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 02100316 CALL ORDER: 001 PROPOSAL ID: E2O71 DISTRICT: 02
COUNTIES : NASSAU

ROAD NAME : MILL & RESURFACE
LIMITS : SR 200

FINPROJ NO(S): 41021617281 (*) FEDERAL AID NO: N/A WORK MIX: ROUTINE MAINTENANCE

TOTAL ROADWAY LENGTH: 0.000 MILES CONTRACT DAYS: 30
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 03/16/10
TOTAL PROPOSAL LENGTH: 0.000 MILES CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A
ACQUIS./FLEXIBLE START TIME : 14

PROPOSAL BUDGET ESTIMATE: $450,000.00

PROPOSAL PACKAGE FEE(PLANS + PROPOSAL): $0.00 PLANS ONLY FEE: $0.00 SPECS ONLY FEE: $0.00

DESCRIPTION:
The work specified in this contract consists of: Supply all materials, equipment, labor, maintenance of traffic, and incidentals necessary to mill & resurface the asphalt pavement on SR 200. Work includes milling, applying tack coat, leveling with SP-9.5 asphalt, resurfacing with Asphaltic Concrete Friction Course (FC-5), painting traffic stripes (all existing markings), installing reflective pavement markers (RPM), removing & disposing of any surplus materials and repairing any traffic loops that may be damaged due to operation.

The costs of all mobilization, equipment, maintenance of traffic, and incidentals necessary to complete job shall be included in the contract pay items listed.

| ALT | ITEM NO. | D E S C R I P T I O N | UNITS | FA/NFA QUANTITY |
|---|---|---|---|---|
| <<<<<<<<<<<< | | SECTION 0001 ASPHALT REPAIR (MECHANICAL) (TN) | | >>>>>>>>>>>> |
| | 0327 70 1 | MILLING EXIST ASPH PAVT, 1" AVG DEPTH | SY | 26,667.000 |
| | 0334 1 13 | SUPERPAVE ASPHALTIC CONC, TRAFFIC C | TN | 730.000 |
| | 0337 7 5 | ASPHALT CONCRETE FRICTION COURSE- INC BIT/RUBBER, FC-5 | TN | 1,470.000 |