BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 02121024 CALL ORDER: 001 PROPOSAL ID: E2Q46 DISTRICT: 02
COUNTIES : ALACHUA , BRADFORD
ROAD NAME : Asphalt Repairs
LIMITS : Alachua & Bradford

FINPROJ NO(S):	FEDERAL AID NO(S):	MAJOR WORK TYPE:
41021317275 (*)	N/A	ROUTINE MAINTENANCE

TOTAL ROADWAY LENGTH: 0.000 MILES
TOTAL BRIDGE LENGTH: 0.000 MILES
TOTAL PROPOSAL LENGTH: 0.000 MILES

CONTRACT DAYS: 365
LETTING DATE : 10/24/12
CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A
ACQUIS./FLEXIBLE START TIME : 15 Days (Acq. Time)

PROPOSAL BUDGET ESTIMATE: $ 284,000.00

PROPOSAL PACKAGE FEE(PLANS + PROPOSAL): $0.00 PLANS ONLY FEE: $0.00 SPECS ONLY FEE: $0.00

DESCRIPTION:
Milling and resurfacing of the roadway and shoulders, etc. at various locations specified in this contract. Some areas will include curb and gutter, and loop assembly removal and replacement. Match existing cross slope. Replace all striping and RPM’s removed by the milling operations. Overlay as necessary to correct cross slopes and dips in the roadway and shoulders. Complete all areas as directed by the Engineer. EXPEDITE DISKETTE BIDDING OR BID EXPRESS MANDATORY.

ALT	ITEM NO.	D E S C R I P T I O N	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 ASPHALT REPAIR (MECHANICAL) (TN)		>>>>>>>>>>>>
	0327 70 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	390.000
	0327 70 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	14,870.000
	0334 1 23	SUPERPAVE ASPH CONC, TRAF C, PG76-22	TN	30.000
	0337 7 42	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	24.000
	0337 7 43	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	1,637.000
	0660 2102	LOOP ASSEMBLY, F&I, TYPE B	AS	12.000
	0660 2106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000
	E101 1 1	MOBILIZATION	LO	5.000