FLORIDA DEPARTMENT OF TRANSPORTATION
BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 02131211 CALL ORDER: 004 PROPOSAL ID: E2S35 DISTRICT: 02
COUNTIES : DUVAL

ROAD NAME : Drainage Project
LIMITS : I-295 NB ramp @ Blanding Blvd.

FINPROJ NO(S):	FEDERAL AID NO(S):	MAJOR WORK TYPE:
41021627246 (*)	N/A	ROUTINE MAINTENANCE

TOTAL ROADWAY LENGTH: 0.000 MILES
TOTAL BRIDGE LENGTH: 0.000 MILES
TOTAL PROPOSAL LENGTH: 0.000 MILES

CONTRACT DAYS: 90
LETTING DATE : 12/11/13
CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A
ACQUIS./FLEXIBLE START TIME : 15 Days (Acq. Time)

PROPOSAL BUDGET ESTIMATE: $ 1,744,000.00

PROPOSAL PACKAGE FEE(PLANS + PROPOSAL): $0.00 PLANS ONLY FEE: $0.00 SPECS ONLY FEE: $0.00

DESCRIPTION:
Repair existing drainage pipe at SR 9A/I-295 northbound off ramp to SR 21/Blanding between milepost 11.000 and 11.668. Work includes rehabilitation of existing 54" diameter x 2,100 feet long (approximately) corrugated metal pipe in accordance with FDOT Standard Specifications, Section 431 Pipe Liner. Pipe liner composition recommended for repair will be Cured-In-Place in accordance with FDOT Standard Specifications, Section 948 Miscellaneous Types of Pipe. Dewatering during Pipe Liner installation will be expected. Also, include polyurethane injection at various locations per plans and Technical Special Provisions. Affected area will also be milled & resurfaced per Roadway Plans to include applying tack coat, resurfacing with Superpave Asphalt, Asphaltic Concrete Friction Course, painting traffic stripes and markings, installing reflective pavement markers (RPM), removing & disposing of any surplus materials. The costs of all mobilization and demobilization, equipment, maintenance of traffic, retro-reflective pavement markers, painted pavement markings, dewatering and incidentals necessary to complete job shall be included in the contract pay items listed. DEBRIS REMOVAL PLAN MUST BE SUBMITTED WITH THE BID. EXPEDITE BIDDING OR BID EXPRESS MANDATORY.

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<		SECTION 0001 ASPHALT REPAIR (MECHANICAL) (TN)		>>>>>>>>>>>
	0327 70 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	19,081.000
	0334 1 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	338.000
	0334 1 23	SUPERPAVE ASPH CONC, TRAFFIC C, PG76-22, PMA	TN	1,761.000
	0337 7 22	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22, PMA	TN	451.000
	0431 1 4	PIPE LINER, OPTIONAL MATERIAL, 49 - 60"	LF	2,100.000
	0906173 3	POLYURETHANE INJECTION SHALLOW POLYURETHANE INJECTION, DEPTH <30'	LB	12,500.000