FLORIDA DEPARTMENT OF TRANSPORTATION
BID SOLICITATION NOTICE AND APPROXIMATE QUANTITIES
(NOT FOR BIDDING PURPOSES)

LETTING ID: 02140723 CALL ORDER: 003 PROPOSAL ID: E2T06 (Construction)
DISTRICT : 02 COUNTIES : MADISON

ROAD NAME : SR 10 (US 90)
LIMITS : AT SR 53N/WASHINGTON ST

FINPROJ NO(S): FEDERAL AID NO(S):
43074715201 (*) N/A

TOTAL ROADWAY LENGTH: 0.025 MILES CONTRACT DAYS: 90
TOTAL BRIDGE LENGTH: 0.000 MILES LETTING DATE : 07/23/14
TOTAL PROPOSAL LENGTH: 0.025 MILES CONTRACT EXECUTION DAYS: 10
SPECIAL START DATE: N/A
BUDGET AMOUNT: $ 172,304.13 ACQUIS./FLEXIBLE START TIME : 150 Acquis.

Please read the full advertisement

DESCRIPTION:
Milling & Resurfacing, Base Work, Shoulder Treatment, Drainage Improvements, Curb & Gutter, Traffic Signals, Highway Signing and other incidental construction at the intersection of SR 10 (US 90) and SR 53 in Madison County. This is a Streamline Plan Quantity contract. EXPEDITE BIDDING OR BID EXPRESS MANDATORY.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at http://www.dot.state.fl.us/equalopportunityoffice/bdi.shtm.

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: http://www.dot.state.fl.us/cc-admin/forms/forms.shtm

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid.

If bidding through Bid Express, please upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in the Expedite application.

BDI Reference Sheet may be found at: http://www.dot.state.fl.us/equalopportunityoffice/bdi.shtm

Bid Bonds of $500 are required for bids over $150,000 and may be in the form of a Cashier#s Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form, Form No. 375-020-09).

A Performance Bond is not required for contracts $250,000.00 and less

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
<<<<<<<<<<<<		SECTION 0001 ROADWAY		>>>>>>>>>>>>
	0101 1	MOBILIZATION (43074715201)	LS	1.000
	0102 1	MAINTENANCE OF TRAFFIC (43074715201)	LS	1.000
	0102 14	TRAFFIC CONTROL OFFICER	MH	16.000
	0102 60	WORK ZONE SIGN	ED	2,070.000
	0102 74 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,340.000
	0102 76	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	270.000
	0102 77	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	1,170.000
	0102 78	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	26.000
	0102 99	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	3.000
	0102104	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	90.000
	0102107 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	90.000
	0104 18	INLET PROTECTION SYSTEM	EA	2.000
	0107 1	LITTER REMOVAL	AC	0.570
	0107 2	MOWING	AC	0.270
	0110 1 1	CLEARING & GRUBBING (43074715201)	LS	1.000
	0110 4	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	238.900

ALT	ITEM NO.	DESCRIPTION	UNITS	FA/NFA QUANTITY
	0120 71	REGULAR EXCAVATION (3-R PROJECTS ONLY) (43074715201)	LS	1.000
	0121 70	FLOWABLE FILL	CY	60.500
	0162 1 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	35.000
	0285711	OPTIONAL BASE, BASE GROUP 11	SY	99.000
	0327 70 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	580.000
	0334 1 23	SUPERPAVE ASPH CONC, TRAFFIC C, PG76-22, PMA	TN	7.600
	0337 7 43	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22, PMA	TN	53.600
	0425 1311	INLETS, CURB, TYPE P-1, <10'	EA	1.000
	0425 6	VALVE BOXES, ADJUST	EA	1.000
	0430175118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	70.000
	0520 1 10	CONCRETE CURB & GUTTER, TYPE F	LF	123.000
	0522 1	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	50.000
	0522 2	CONC SIDEWALK AND DRIVEWAYS, 6" THICK	SY	167.000
	0527 2	DETECTABLE WARNINGS	SF	10.000
	0570 1 2	PERFORMANCE TURF, SOD	SY	35.000
	0710 11111	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	NM	0.096
	0710 11123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	LF	377.000
	0710 11125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	LF	49.000
	0710 11211	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	NM	0.133
	0999 25	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43074715201)	LS	1.000
<<<<<<<<<<<		SECTION 0002 SIGNING		>>>>>>>>>>>
	0700 1 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700 1 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0700 3201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0710 90	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43074715201)	LS	1.000
<<<<<<<<<<<		SECTION 0003 SIGNALIZATION		>>>>>>>>>>>
	0630 2 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	77.000
	0630 2 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	365.000
	0632 7 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635 2 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0646 1 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
	0649 31203	MAST ARM,F&I, WIND SPEED-130,SINGLE ARM,W/0 LUMINAIRE-60	EA	1.000
	0650 1311	TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, ALUMINUM	AS	2.000
	0653192	PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 2 DIRECTIONS	AS	1.000
	0660 2106	LOOP ASSEMBLY, F&I, TYPE F	AS	3.000
	0665 1 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	2.000
	0690100	SIGNAL EQUIPMENT MISCELLANOUS REMOVE	PI	1.000