Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02160720 Call Order: 002 Proposal: E2V53 District:02

Counties: DUVAL

Road Name: JACKSONVILLE MAINT - ROUTINE MAINTENANCE

Limits: SR 212 Beach Boulevard, 72190, station 528+40 to station 530+00

Project(s): 41021667230(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	30
Total Bridge Length:	0.000 Miles	Letting Date:	07/20/16
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days (Acq. Time)

Proposal Budget Estimate: $200,000.00

Please read the full advertisement

Description:

Removal of approximately 160 linear feet of existing 48" corrugated metal pipe, furnishing and installing new 48" RCP Class III pipe, and connecting to existing manholes. The existing pipe invert elevation is approximately 8.5' below existing finish grade. In order to facilitate replacement of pipe, work will also include removal and replacement of existing Type "F" curb and gutter (approximately 160 linear feet) and a portion of travel lane within project limits. Project location is SR 212 Beach Boulevard eastbound right turn lane for Highland Glen Community (station 528+40 to station 530+00). DEBRIS DISPOSAL PLAN MUST BE SUBMITTED WITH THE BID. BID EXPRESS MANDATORY.

Call Order: 002 Proposal: E2V53

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0285-714-	OPTIONAL BASE, BASE GROUP 14	SY	220.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	25.000
	0337- 7- 43	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76 -22, PMA	TN	20.000
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	160.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	160.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	3.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	480.000