

FLORIDA DEPARTMENT OF TRANSPORTATION
TABULATION OF BIDS

DATE : 07/07/09
PAGE : 004 -4

CALL ORDER : 004
LETTING DATE : 06/24/09 2:00 P.M.
SET-ASIDE :
CONTRACT TIME : 120
PROPOSAL ID : E2L17
DISTRICT : 02
U/R CODE :
WORKING DAYS (AVAILABLE DAYS)

PROPOSAL DESC :
DESIGN BUILD - Safe Routes to School Sidewalk in Perry,
Taylor County, Florida.

In all locations with proposed sidewalks, the sidewalk should be five (5) feet wide and four (4) inches thick. Ramps and tactile domes to be replaced/installed in the locations where the proposed sidewalk ties into the existing or proposed crosswalks. The location of stop bars and Stop signs to be adjusted as necessary to accommodate the installation of the proposed crosswalks.

Veterans Drive from Jefferson Street to Clark Street:

- New sidewalk installed on the south side of Veterans Drive from Jefferson Street to Center Street to tie the existing sidewalks. Locate sidewalk in line with the existing sidewalk except from Washington Street to Orange Street, where it is to be located 2.5 feet from the edge of pavement to avoid a large tree east of Washington Street.
- Install crosswalks across the south leg of Jefferson Street. Advanced pedestrian crossing signage should be installed for the crosswalk.
- Install crosswalks across the south leg of Washington Street
- Install crosswalks across the south leg of Orange Street.
- Install crosswalks across the south leg of Center Street.
- Remove crosswalk across the west leg of Center Street.
- Extend sidewalk installed on the west side of Aquinaldo Avenue to tie into existing sidewalk on the east side of Aquinaldo Avenue
- Extend sidewalk installed on west side of Bulldog Loop to tie into existing sidewalk on the east side of Bulldog Loop.
- Remove crosswalk across Veterans Drive at Margurite Street (west leg of intersection)
- Lafayette Street from Jefferson Street to Bulldog Loop:
 - Remove crosswalk across the west leg of Center Street.
 - Remove the section of sidewalk that extends north from the existing sidewalk approaching Center Street.
 - Extend sidewalk installed on west side of Jeff Davis Street to tie into existing sidewalk on the east side of Jeff Davis Street. Relocate crosswalk in front of the stop bars and stop signs.
 - Extend sidewalk installed on west side of Aquinaldo Avenue to tie into existing sidewalk on the east side of Aquinaldo Avenue.
 - Extend sidewalk installed on west side of Peacock Avenue to tie into existing sidewalk on the east side of Peacock Avenue.
 - Extend sidewalk installed on west side of Manilla Avenue

to tie into existing sidewalk on the east side of Manilla Avenue. Relocate crosswalk in front of the stop bars and stop signs.

Clark Street from Main Street to Pinecrest Street:

- Extend sidewalk installed on the north side of Bay Street to tie into existing sidewalk and existing crosswalk on the west side of Clark Street.
- Remove two existing crosswalks south of Veterans Drive.
- Relocate stop bar and Stop sign at the west approach to the Veterans Drive to meet the minimum spacing requirement.
- Install a small section of sidewalk on the south side of Veterans Drive to tie the existing sidewalk on the west side of Clark Street into the existing crosswalk across the west leg of the intersection.
- Install sidewalk along the west side of Clark Street from the crosswalk across the west leg of the Veterans Drive intersection north to the crosswalk north of the Veterans Drive intersection.
- Install sidewalk along the east side of Clark Street from the crosswalk north of the Veterans Drive intersection north to the end of the existing sidewalk at the Perry Primary School faculty parking lot.
- New sidewalk installed on the north side of Pinecrest Street to tie the existing sidewalk along the north side of Pinecrest Street into the existing crosswalk across the east leg of the intersection. Relocate stop bar and Stop sign for the south approach behind the existing crosswalk.

Main Street from Jefferson Street to Clark Street:

- Extend sidewalk installed on west side of Aquinaldo Avenue to tie into existing sidewalk on the east side of Aquinaldo Avenue. Relocate crosswalk in front of the stop bars and stop signs.
- New sidewalk installed on the south side of Main Street from the end of the existing sidewalk approximately 170' (driveway of 603 Main Street) to Clark Street.
- Install crosswalks across the south leg of Arena Avenue.
- Install crosswalks across the south leg of Blair Avenue.
- Install crosswalks across the south leg of Hinley Avenue
- Install crosswalks across the south leg of Elmo Scott Avenue.
- A pedestrian bridge walk is necessary to allow the sidewalk to cross the creek east of Peacock Avenue.
- Substantial clearing and grubbing may be necessary between Peacock Avenue and Arena Avenue due to the heavy foliage in the right-of-way (stay within right-of-way).
- The fence at 1005 Main Street is in the right-of-way and will need to be relocated.

FINPROJ(S) : 42324415201 (*) F.A. NO. : SRTS024A COUNTIES : TAYLOR

LOCAL NAME : TAYLOR CO/SAFE ROUTE ROAD NAME :

PROJ LIMITS : TO SCHOOLS TCM AND PERRY PRIMARY

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) SANTA CRUZ CONSTRUCTION, IN		(2) SEMPER FI SERVICES, LLC		(3) M OF TALLAHASSEE, INC.	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY							
0005 0999 2 LUMP SUM CONTRACT, ALTERNATIVE BIDDING 42324415201	LUMP	147950.00000	147950.00	168441.28000	168441.28	168500.00000	168500.00
0010 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 42324415201	LUMP	13900.00000	13900.00	13900.00000	13900.00	13900.00000	13900.00
SECTION 0001 TOTALS			\$ 161,850.00		\$ 182,341.28		\$ 182,400.00
CONTRACT TOTALS			\$ 161,850.00		\$ 182,341.28		\$ 182,400.00

FLORIDA DEPARTMENT OF TRANSPORTATION
 TABULATION OF BIDS

DATE : 07/07/09
 PAGE : 004 -7

CALL ORDER: 004

PROPOSAL ID: E2L17

LETTING DATE: 06/24/09 2:00 P.M.

DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CURT'S CONSTRUCTION, INC		(5) TRANSPORTATION STRUCTURES,		(6) ONAS CORPORATION	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY							
0005 0999 2 LUMP SUM CONTRACT, ALTERNATIVE BIDDING 42324415201	LUMP	171585.76000	171585.76	176000.00000	176000.00	196082.35000	196082.35
0010 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 42324415201	LUMP	13900.00000	13900.00	13900.00000	13900.00	13900.00000	13900.00
SECTION 0001 TOTALS			\$ 185,485.76		\$ 189,900.00		\$ 209,982.35
CONTRACT TOTALS			\$ 185,485.76		\$ 189,900.00		\$ 209,982.35

FLORIDA DEPARTMENT OF TRANSPORTATION
 TABULATION OF BIDS

DATE : 07/07/09
 PAGE : 004 -8

CALL ORDER: 004

PROPOSAL ID: E2L17

LETTING DATE: 06/24/09 2:00 P.M.

DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CDM CONTRACTING, INC.		(8) ANDERSON COLUMBIA CO., INC.		(9) SAYAR ENTERPRISES, INC. DBA SOU	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY							
0005 0999 2 LUMP SUM CONTRACT, ALTERNATIVE BIDDING 42324415201	LUMP	228495.50000	228495.50	244390.00000	244390.00	299000.00000	299000.00
0010 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 42324415201	LUMP	13900.00000	13900.00	13900.00000	13900.00	13900.00000	13900.00
SECTION 0001 TOTALS			\$ 242,395.50		\$ 258,290.00		\$ 312,900.00
CONTRACT TOTALS			\$ 242,395.50		\$ 258,290.00		\$ 312,900.00

CERTIFIED TO BE A TRUE COPY AND APPROVED BY Jane E. Jones-Redd
 District Contracts Administrator

7-7-2009
 DATE

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

ACTUAL COMMITMENT AND FINAL EXECUTION OF THE CONTRACT IS CONTINGENT UPON AN APPROVED LEGISLATIVE BUDGET AND FUNDS AVAILABILITY.

POSTING BEGINS JULY 7, 2009 AT 4:15 P.M. AND ENDS JULY 10, 2009 @ 5:00 P.M.