



Florida Department of Transportation

RICK SCOTT
GOVERNOR

1109 S. Marion Avenue
Lake City, Florida 32025-5874

ANANTH PRASAD P.E.
SECRETARY

May 31, 2012

To: Prospective Bidders

Addendum No.: **3, E2O42, Financial Project # 21045825201**
(SR 206 / ICWW Matanzas BR # 780090) Highway Signing, Bridges, Structural, Mechanical, Electrical and other incidental construction on SR 206 Crescent Beach Bridge (#780090) in St. Johns County.

Attached is Supplemental Specifications Package Number Two and a Question with Answer for the following:

SECTION T465 – MOVABLE BRIDGES (of the Supplemental Specifications Package Number One), page(s) 14-30, is deleted and the following substituted:

PLAN REVISIONS NUMBER 2:

<u>Sheet No(s).</u>	<u>Rev. Date</u>	<u>Description</u>
B-1	5-25-12	Listed Revisions
B1-2	5-25-12	See Summary of Quantities Table below
B1-15	5-25-12	Added Brake Torque Note
B1-75	5-25-12	Added additional window detail

SUPPLEMENTAL SPECIFICATIONS PACKAGE NUMBER 2

<u>Sheet No(s).</u>	<u>Rev. Date</u>	<u>Description</u>
1-20	5-25-12	Revised TSP T465

SUMMARY OF QUANTITIES:

Pay Item	Sheet No.	Add. / Del. / Rev.	Old Quantity	New Quantity
465-21	B-2	Add		235

QUESTION: Ductless HVAC System: Ref Sheets B1-76 thru B1-79 & Spec T512.28.6 neither the specifications nor the plans provides information on the desired brand, model number or tonnage of the new ductless HVAC system. Please provide desired brand, model number and tonnage.

ANSWER:

DUCTLESS SPLIT HEAT PUMP SYSTEM SCHEDULE			
Air Handling Unit Data			
Mark	-	DAHU - 1	DAHU - 2
Cooling Capacity - Total	BTUH	18000	18000
Supply Air (Low/Med/High)	CFM	500/570/630	470/560/690
Heating Capacity - Total	BTUH	18000	18000
Back Up Heater	KW		
Electrical Service	VOLT I c1 /HZ	NOTE 1	208/1/60
Fan Motor	FLA	0.26	0.50
Remote Air Cooled Condensing Unit Data			
Mark	-	DCU - 1	DCU-2
Outdoor Temp.		95	95
Electrical	VOLT/ 0 /HZ	208/1/60	208/1/60
MCA	-	11	12.1
MOCP	-	20	20
SEER (HSPF)	-	13 (7.7)	13 (7.7)
Notes	-	2	2;3
Notes:			
1 - Indoor unit is powered from outdoor unit.			
2 - Provide required length of insulated refrigerant piping.			
3 - Provide built-in condensate pump.			

If you are a BID DOCUMENT HOLDER for the subject project, please go to the Online Ordering Web Site at <https://www3.dot.state.fl.us/ContractProposalProcessingOnlineOrdering/> to download E2O42 Amendment003 for this Bid Document from your Order History.

If you are a BID DOCUMENT HOLDER, please acknowledge receipt of this Addendum in Expedite Bid by opening the Acceptance of Bidding Acknowledgements folder and confirming your acknowledgement of Amendment and Addenda files. Failure to load all amendment files will cause the bid to be rejected.

 Company Name

 Signature

 Date

Thanks,

Patsy Elkins, CPPB
 Contracts Coordinator
 Phone: 386-758-3703
 Fax: 386-758-3791