Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03150813 Call Order: 001 Proposal: E3N41 District:03

Counties: LEON

Road Name: SR 8 (I-10) OCHLOCKNEE RIVER BRIDGE BRIDGE NO. 550089

Limits: Midpoint

Project(s): 42016125201(*) Federal Aid No: N/A

Total Roadway Length:	0.229 Miles	Contract Days:	45
Total Bridge Length:	0.458 Miles	Letting Date:	08/13/15
Total Proposal Length:	0.687 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30 Days (Acq. Time)

Proposal Budget Estimate: $336,010.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of installing Rip-Rap (Bank and Shore) as a scour countermeasure for two bridge piers and two bridge bents each at Bridge Numbers 550050 and 550089 on SR 8 (I-10) in Leon County. PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

Call Order: 001 Proposal: E3N41

ALT	Item	Description	Unit	Quantity
Section 0001 STRUCTURES				
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,733.800
	0530- 74-	BEDDING STONE	TN	793.200
Section 0002 ROADWAY				
	0101- 1-	MOBILIZATION (42016125201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42016125201)	DA	45.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	90.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	45.000
	0104- 10- 3	SEDIMENT BARRIER	LF	899.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	867.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42016125201)	LS	1.000