Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03150813 Call Order: 008 Proposal: E3O73 District:03

Counties: DIST/ST-WIDE, HOLMES, WALTON

Road Name: PONCE DE LEON OPER ROUTINE MAINTENANCE
ROUTINE MAINTENANCE

Limits: P.B. Shoulder Rework SR8 (I-10)

Project(s): 42214317267(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	0
Total Bridge Length:	0.000 Miles	Letting Date:	08/13/15
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: $500,000.00

Please read the full advertisement

Description:

The improvements under this contract consist of the refurbishment, reshaping and establishment of turf along roadway shoulders, front slopes and back slopes of designated areas along SR 8 (I-10) within Walton and Holmes Counties. Work specified is to establish a good stand of turf in order to prevent shoulder drop off hazards and establish slope stabilization along front and back slopes to prevent drainage failures due to silt buildup. Turf establishment shall be accomplished utilizing sod placement, while some areas will require seeding operations. Specific locations shall be include in a subsequent Work Documents upon award and execution of this contract. This contract has a budgetary ceiling of $500,000.00 Mobilization and Maintenance of Traffic shall be incidental to the bid items.

Call Order: 008 Proposal: E3O73

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0570- 1- 1	PERFORMANCE TURF	SY	114,311.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	25,878.000
	E577- 70-	SHOULDER REWORK	SY	214,468.000