

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03150813 Call Order: 012 Proposal: E3O77-R0 District:03
Counties: DIST/ST-WIDE, ESCAMBIA, OKALOOSA, SANTA ROSA
Road Name: MILTON OPERATIONS ROUTINE MAINTENANCE
ROUTINE MAINTENANCE
Limits: Traffic Ops. Work Requests
Project(s): 42214227254(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: 0
Total Bridge Length: 0.000 Miles Letting Date: 08/13/15
Total Proposal Length: 0.000 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Days

Proposal Budget Estimate: \$100,000.00

Please read the full advertisement

Description:

The improvements under this contract consist of installation of information signs (Single and multi-post), installation and/or refurbishment of traffic markings, and removal and/or replacement of retro-reflective pavement markers within the Department's right of way in Escambia, Santa Rosa and Okaloosa County. This is a pushbutton contract with all work described herein being performed on a call out basis. The overall budgetary ceiling on this contract shall not exceed \$100,000.00. The work being performed in this package needs a Contractor Experience form number 850-070-06 to be submitted with the bid.

Call Order: 012 Proposal: E3O77-R0

ALT	Item	Description	Unit	Quantity
Section 0001 SIGNS(GRND SIGNS 30 SQ FT OR LESS)(UN)				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	5.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	5.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	5.000
	0700- 1- 18	SINGLE POST SIGN, F&I GROUND MOUNT, IN-STREET FLEXIBLE POST SIGN	AS	5.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870, UP TO 12 SF	AS	5.000
	0700- 1- 32	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870, 12-20 SF	AS	5.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	5.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0700- 2- 11	MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	5.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	5.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	5.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	5.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	5.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	5.000
	0700- 2- 17	MULTI- POST SIGN, F&I GROUND MOUNT, 201-300 SF	AS	5.000
	0700- 2- 18	MULTI- POST SIGN, F&I GROUND MOUNT, 301-400 SF	AS	5.000
	0700- 2- 50	MULTI- POST SIGN, F&I GROUND MOUNT, RELOCATE	AS	5.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	5.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	5.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	5.000

Call Order: 012 Proposal: E3077-R0

ALT	Item	Description	Unit	Quantity
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	5.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	5.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	5.000
	0700- 3-107	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 201-300 SF	EA	5.000
	0700- 3-108	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 301-400 SF	EA	5.000
	0700- 3-109	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 401-500 SF	EA	5.000
	0700- 3-403	SIGN PANEL, INSTALL, 21-30 SF	EA	5.000
	0700- 3-405	SIGN PANEL, INSTALL, 51-100 SF,	EA	5.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	5.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	5.000
	0700- 3-503	SIGN PANEL, RELOCATE, 21-30 SF	EA	5.000
	0700- 3-504	SIGN PANEL, RELOCATE, 31-50 SF	EA	5.000
	0700- 3-505	SIGN PANEL, RELOCATE, 51-100 SF	EA	5.000
	0700- 3-506	SIGN PANEL, RELOCATE, 101-200 SF	EA	5.000
	0700- 3-507	SIGN PANEL, RELOCATE, 201-300 SF	EA	5.000
	0700- 3-508	SIGN PANEL, RELOCATE, 301-400 SF	EA	5.000
	0700- 3-509	SIGN PANEL, RELOCATE, 401-500 SF	EA	5.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGEABLE AND URBAN ISLAND	GM	0.050
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	250.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	250.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	250.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	2.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	250.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	5.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROWS	EA	5.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	2.000
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	2.000
	0711- 15-202	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES YELLOW, SOLID, 8"	GM	2.000
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.000
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.000
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.000

Call Order: 012 Proposal: E3077-R0

ALT	Item	Description	Unit	Quantity
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	2.000
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.000
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS	SF	25,000.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REM AND REPL)(CLASS B)	EA	1,000.000