

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03150910 Call Order: 009 Proposal: E3O98-R0 District:03
Counties: DIST/ST-WIDE, GADSDEN, LEON
Road Name: MIDWAY OPERATIONS ROUTINE MAINTENANCE - ROUTINE MAINTENANCE
Limits: Misc. Concrete Repair
Project(s): 42215117262(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: Thru 6/30/2016
Total Bridge Length: 0.000 Miles Letting Date: 09/10/15
Total Proposal Length: 0.000 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 15 Days
Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

Description:

This contract is to be used for miscellaneous concrete repair in Leon and Gadsden Counties for removal and replacement of sidewalk, concrete ditch, and slope paving. This contract excludes concrete repair at locations within or adjoining Tallahassee city limits which require night work due to lane closure restrictions. Additional miscellaneous concrete items to be removed and replaced include, but are not limited to, driveways, curb and gutter, valley gutters, curb ramps, and mitered end sections. Also included are associated items including, but not limited to, borrow material, miscellaneous asphalt, commercial material for driveways, detectable warning surfaces on sidewalks, minor drainage repairs, pedestrian handrails, and sodding. All debris generated shall be removed and disposed of by the contractor, at locations provided by the contractor, in compliance with all Federal, State, and Local laws and regulations. This contract has a budgetary ceiling of \$400,000.00. All work will be conducted on a call out basis, authorized by Work Document, with an anticipated six (6) call outs during the course of this contract. Mobilization is incidental to the other pay items listed within the contract.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 009 Proposal: E3O98-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0102- 3-	COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	CY	20.000
	0102- 60-	WORK ZONE SIGN	ED	1,200.000
	0102- 61-	BUSINESS SIGN	EA	20.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	20.000
	0102- 77-	HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	ED	800.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	40.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	2,000.000
	0104- 10- 3	SEDIMENT BARRIER	LF	500.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0110- 4-	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	6,000.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	1,800.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	5.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	5.000
	0430-984-121	MITERED END SECTION, OPTIONAL ROUND, 12" SD	EA	5.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	5.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	5.000
	0430-984-623	MITERED END SECTION, OPTIONAL OTHER - ELLIP/ARCH, 15" SD	EA	2.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	2.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	100.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	100.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	500.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	500.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	500.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	2,000.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	500.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	3,200.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	350.000
	0527- 2-	DETECTABLE WARNINGS	SF	500.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	50.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	400.000
	0570- 1- 1	PERFORMANCE TURF	SY	5,000.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,500.000
	E102- 1- 2	MAINTENANCE OF TRAFFIC	DA	200.000
	E110- 70-	REMOVAL OF FLEXIBLE PAVEMENT	SY	500.000