Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03151008 Call Order: 005 Proposal: E3P02 District:03

Counties: DIST/ST-WIDE, HOLMES

Road Name: SR 79

Limits:

Project(s): 42214317264 Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	Thru June 30, 2016
Total Bridge Length:	0.000 Miles	Letting Date:	10/08/15
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: $300,000.00

Please read the full advertisement

Description:

The improvements under this Contract consist of reshaping ditches along SR 79 in Holmes County at designated locations, from Son-In-Law Road to Alabama State Line, as shown in the appendices. These ditches are non-typical and should be re-graded to +/- 3 inches of the original flow line to create a free and unobstructed flow of drainage water. For the purposes of this contract, the original flow line is considered to be the linear projection along the ditch bottom between the invert elevations of immediately adjacent drainage structures, as shown in the appendices. This is a site-specific contract, and work will be issued by work document. Mobilization and Maintenance of Traffic shall be incidental to the bid items provided.

Call Order: 005 Proposal: E3P02

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0104- 10- 3	SEDIMENT BARRIER	LF	500.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	200.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	50.000
	E110- 2-	CLEARING & GRUBBING	AC	3.000
	E120- 10- 2	CLEAN AND RESHAPE DITCH (HAUL)	LF	26,410.000
	E570- 2-	SEED & MULCH	SY	300.000
	E570- 5-	FERTILIZER	TN	0.250
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	5,000.000
	E575- 1-	SODDING	SY	600.000