Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03151008 Call Order: 010 Proposal: E3P08 District:03

Counties: DIST/ST-WIDE, JACKSON, WASHINGTON

Road Name: MARIANNA MAINTENANCE - JACKSON & WASHINGTON

Limits: 53040000

Project(s): 42212217252(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	180
Total Bridge Length:	0.000 Miles	Letting Date:	10/08/15
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: $500,000.00

Please read the full advertisement

Description:

The work under this contract consists of fence line pruning, tree trimming, and tree and brush removal along Interstate 10 (State Road 8) in Jackson and Washington Counties. Cut and remove trees (greater than or equal to 6 inches in diameter – measured as diameter at breast height) and brush within the right-of-way, adjacent to the fence. Create a continuous corridor with minimum dimensions of 10 feet wide and 15 feet high. No brush, limbs or debris shall be left protruding either horizontally or vertically from the fence line in accordance with the aforementioned dimensions. All vegetation greater than ¼ inch in diameter, shall be removed from the fence, and line trimmers shall be utilized at the base of the fence, concurrent with the removal operation. This work shall be performed without the use of a flail type mower. At no time will tree trimming operations get over two (2) days ahead of the debris removal operation. If this does occur, the tree trimming operation will stop until the debris removal operation gets within these limits. All work shall meet the requirements of Federal, State, and local laws and environmental standards. Maintenance of Traffic will be incidental to the pay items listed.

Call Order: 010 Proposal: E3P08

ALT	Item	Description	Unit	Quantity
Section 0001 TREE TRIMMING AND REMOVAL (MH)				
	E101- 1- 1	MOBILIZATION	LO	1.000
	E580-332- 99	TREE AND BRUSH REMOVAL	AC	1,725.000