Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03151210 Call Order: 005 Proposal: E3P23-R0 District:03

Counties: DIST/ST-WIDE, JACKSON, WASHINGTON

Road Name: MARIANNA MAINTENANCE - JACKSON & WASHINGTON

Limits: 53040000

Project(s): 42212217203(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	Thru December 31, 2016
Total Bridge Length:	0.000 Miles	Letting Date:	12/10/15
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: $350,000.00

Please read the full advertisement

Description:

The Improvements in this Contract consist of miscellaneous concrete repair to be performed on a call out basis. The work will consist primarily of the removal and replacement of damaged sidewalk, curb and gutter, ditch pavement, driveways, inlet tops, curb ramps and mitered end slabs. Work may include furnishing borrow material, miscellaneous asphalt repair and seeding and sodding around completed areas. There will be an anticipated four (4) callouts during the course of this contract. All work shall meet the requirements of Federal, State, and local laws and environmental standards. Maintenance of Traffic and Mobilization will be incidental to the pay items provided. This will be a work document driven contract, and will have a budgetary ceiling of $350,000.00.

Call Order: 005 Proposal: E3P23-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0104- 10- 3	SEDIMENT BARRIER	LF	2,000.000
	0110- 4-	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	1,000.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.000
	0430-990-	MITERED END SECT, REPLACE GRATE	EA	5.000
	0430-991- 1	MITERED END SECT, REPLACE SLAB- MAINTENANCE USE ONLY	CY	150.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	10.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	10.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,500.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	100.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	2,000.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	100.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	25.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	25.000
	0524- 2- 1	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 3"	SY	50.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT,NON REINFORCED, 4"	SY	50.000
	0527- 2-	DETECTABLE WARNINGS	SF	10.000
	E570- 2-	SEED & MULCH	SY	100.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	25.000
	E575- 1-	SODDING	SY	450.000