Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03160211 Call Order: 005 Proposal: E3P54 District:03

Counties: CALHOUN

Road Name: SR 69 & SR 71

Limits: Calhoun

Project(s): 40716695225(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	Thru 8/31/17
Total Bridge Length:	0.000 Miles	Letting Date:	02/11/16
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: $55,000.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of placement of permanent striping on completed construction jobs on various roadways, as shown in the Appendix. A Contractor Experience in Pavement Markings Form, No. 850-070-06, is required to be submitted with bid.

Call Order: 005 Proposal: E3P54

ALT	Item	Description	Unit	Quantity
Section 0002 Roadway				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	DA	1.000
	0546- 72- 52	RUMBLE STRIPS, GROUND-IN, 16" CENTERLINE USED WITH RUMBLE STRIPE	GM	0.551
	0546- 72- 53	RUMBLE STRIPS, GROUND-IN, 8" EDGELINE USED WITH RUMBLE STRIPE	GM	1.131
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	16.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.169
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.398
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.551
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.259
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.135
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.084
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.084