Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03160211 Call Order: 007 Proposal: E3P57 District:03

Counties: DIST/ST-WIDE, JACKSON

Road Name: SR 75 (US 231) Asphalt Repair

Limits: 53030000

Project(s): 42212217259(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	30
Total Bridge Length:	0.000 Miles	Letting Date:	02/11/16
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: $400,000.00

Please read the full advertisement

Description:

The Improvements under this Site-Specific Contract consist of milling & resurfacing the southbound outside travel lane of State Road 75 (US 231), between State Road 73 and the curb and gutter section north of Cottondale, as shown in the Appendices. Replace raised pavement markers (RPMs) and painted pavement markings as part of this contract. A Contractor Experience Form (850-070-01), Experience in Asphalt Paving, is required to be submitted with bid.

Call Order: 007 Proposal: E3P57

ALT	Item	Description	Unit	Quantity
Section 0002 ASPHALT REPAIR (MECHANICAL) (TN)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	DA	1.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	16,973.000
	0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	907.000
	0327- 70- 8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	1,120.000
	0334- 1- 23	SUPERPAVE ASPH CONC, TRAFFIC C, PG76-22, PMA	TN	968.200
	0337- 7- 22	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22, PMA	TN	1,082.100
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.700
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	2.700
	E102- 10-	OFF-DUTY LAW ENFORCEMENT OFFICER	MH	50.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REM AND REPL)(CLASS B)	EA	357.000