Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03160414 Call Order: 005 Proposal: E3P94 District:03

Counties: DIST/ST-WIDE, WALTON

Road Name: PONCE DE LEON ROUTINE MAINTENANCE - SR 83 (US 331)

Limits: Walton

Project(s): 42214317289(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	30
Total Bridge Length:	0.000 Miles	Letting Date:	04/14/16
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	Std. 15 Days

Proposal Budget Estimate: $80,000.00

Please read the full advertisement

Description:

The Improvements under this Contract include changing roadway features in Walton County, along SR 83 (US 331), north of SR 30 (US 98), from approximately MP 0.784 to MP 0.830, to better collect storm water from the roadway and convey it to the existing drainage system. This work includes the removal of existing concrete pavement, sidewalk, and curb and gutter, and the construction of trench drain, type F curb & gutter, sidewalk and connection pipe between the proposed trench drain and the existing inlet structure. Prepared soil layer and sodding are to be installed at locations identified within the plans. A Contractor Experience in Drainage Repair Form, No. 850-070-05 is required to be submitted with bid. Concrete Curb and Gutter, Type F shall be incidental to Trench Drain pay item 436-1-1 from Sta. 2+70.00 to 3+85.00 as shown in the plans.

Call Order: 005 Proposal: E3P94

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	180.000
	0102- 71- 13	BARRIER WALL, TEMPORARY, F&I, LOW PROFILE, CONCRETE	LF	300.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,050.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	30.000
	0104- 10- 3	SEDIMENT BARRIER	LF	357.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0110- 4-	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	26.000
	0162- 1- 11	PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	SY	267.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	115.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	113.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	156.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	267.000