

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 03160609 Call Order: 004 Proposal: E3P73 District:03  
 Counties: JEFFERSON  
 Road Name: SR 8 (I-10) AT SR 59 LLOYD EXIT LIGHTING - LIGHTING  
 Limits: AT SR 59 LLOYD EXIT LIGHTING  
 Project(s): 22266815201(\*) Federal Aid No: 0104145I  
 Total Roadway Length: 0.538 Miles Contract Days: 120  
 Total Bridge Length: 0.000 Miles Letting Date: 06/09/16  
 Total Proposal Length: 0.538 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 120 Days Acquis.

Proposal Budget Estimate: \$757,195.00

Please read the full advertisement

**Description:**

The Improvements under this District Contract consist of providing the labor, material, and equipment necessary to complete the Interchange High Mast Lighting project for SR 8 (I-10) at CR 59 Lloyd Exit in Jefferson County. Details of this project are shown in the Contract Plans. The summary of pay items for this project is listed in the Plans. PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

**Call Order: 004 Proposal: E3P73**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Lighting</b>				
	0101- 1-	MOBILIZATION (22266815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (22266815201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,440.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,200.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	720.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	480.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	8,490.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	340.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	27.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	4.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	8.000
	0639- 1-111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY	AS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	2,895.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	9,660.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	25,230.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	4.000
	0715- 19-133	HIGH MAST LIGHT POLE COMPLETE, F&I, WIND SPEED-110 MPH, POLE HEIGHT 120'	EA	11.000
	0715-500- 2	POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST	EA	11.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22266815201)	LS	1.000