Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03160609 Call Order: 005 Proposal: E3P74 District:03

Counties: OKALOOSA

Road Name: SR 8 (I-10) AT CR 189 HOLT EXIT LIGHTING - LIGHTING

Limits: AT CR 189 HOLT EXIT LIGHTING

Project(s): 22271315201(*) Federal Aid No: 0101217I

Total Roadway Length:	0.697 Miles	Contract Days:	120
Total Bridge Length:	0.000 Miles	Letting Date:	06/09/16
Total Proposal Length:	0.697 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120 Days Aquis.

Proposal Budget Estimate: $682,428.00

Please read the full advertisement

Description:

The Improvements under this District Contract consist of providing the labor, material, and equipment necessary to complete the Interchange High Mast Lighting project for SR 8 (I-10) at CR 189 Holt Exit in Okaloosa County. Details of this project are shown in the Contract Plans. The summary of pay items for this project is listed in the Plans. PRE-QUALIFICATION IS REQUIRED TO BID ON THIS PROJECT.

Call Order: 005 Proposal: E3P74

ALT	Item	Description	Unit	Quantity
Section 0001 Lighting				
	0101- 1-	MOBILIZATION (22271315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (22271315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,440.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,200.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	720.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	480.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	7,360.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	400.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	25.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	4.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	8.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	1.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	3,210.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	3,945.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	21,390.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	4.000
	0715- 19-123	HIGH MAST LIGHT POLE, F&I, WIND SPEED-130 MPH, POLE 120'	EA	10.000
	0715-500- 2	POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST	EA	10.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (22271315201)	LS	1.000