Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 03161110 Call Order: 006 Proposal: E3Q31 District:03

Counties: DIST/ST-WIDE, WALTON

Road Name: PONCE DE LEON OPER ROUTINE MAINTENANCE

Limits: Walton County

Project(s): 42214317285(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	45
Total Bridge Length:	0.000 Miles	Letting Date:	11/10/16
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	15 Days

Proposal Budget Estimate: $150,000.00

Please read the full advertisement

Description:

The work under this Site-Specific Contract consists of pipe liner installation, dewatering, desilting and removal of debris, while maintaining the layout and features of an existing cross drain on State Road 20, MP 22.393 (approximately 0.02 miles east of J.W. Hollington Road) in Walton County. Cross drain is corrugated metal pipe (approximately 7 feet by x 12 feet x 63 feet). Provide a DVD of work performed to the Department when work is completed. Maintenance of Traffic, Mobilization, and Restoration of site to current conditions shall be incidental to the pay items listed. A Contractors Experience in Drainage Repair form (850-070-05) must accompany the bid.

Call Order: 006 Proposal: E3Q31

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0104- 10- 3	SEDIMENT BARRIER	LF	100.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	100.000
	0430- 94- 5	DESILTING PIPE, 61" OR GREATER	LF	63.000
	0431- 1- 5	PIPE LINER, OPTIONAL MATERIAL, 61" AND GREATER	LF	63.000